


- 📍 Office Corner  
Block C, 184 Lancaster Road,  
Gordon's Bay,  
7140
- ☎ 066 105 1226
- ✉ [techq.development@outlook.com](mailto:techq.development@outlook.com)
- 📞 086 474 1937
- 🌐 [www.techq-development.com](http://www.techq-development.com)



## Professional Engineering Services

Investigation and Structural Engineering  
Remedial Concepts to Erf 18471, Mossel Bay  
House Bernard

## Report – Rev 0

26 April 2024

Contact Person: **Melt Badenhorst** (Pr.Tech.Eng)

## Document Control Sheet

<b>Client Project Reference</b> Erf 18471, Mossel Bay (House Bernard)		<b>Internal Project Number</b> TechQ – 023
<b>Title</b> Professional Engineering Services: Forensic Investigation and Structural Engineering Remedial Concepts		
<b>Project Stage</b> Investigation and Concept Remedial Proposals		
Version	Date	Comment
Rev 0	26 April 2024	Report submitted
<b>Prepared For:</b> The Project Manager <b>National Home Builders Registration Council</b> 27 Leeuwkop Road, Sunninghill <b>Johannesburg</b> 2191		
<b>Prepared By:</b> <b>TechQ Development (Pty) Ltd</b> OFFICE CORNER – Block C <b>184 Lancaster Road</b> Gordon's Bay <b>7140</b>		
<b>Compiled By: Consultant</b>   <b>MJ Badenhorst</b> (Pr.Tech.Eng) <b>ECSA</b> : Pr. Reg No. 200270009 <b>NHBRC</b> : 601551		<b>Reviewed By: (Client – NHBC)</b>

## Table of Contents

<b>EXECUTIVE SUMMARY</b> .....	1
<b>1 PROJECT LOCALITY, SCOPE AND INFORMATION</b> .....	2
1.1 Project Locality .....	2
1.2 Scope of Work.....	2
1.3 Information Provided (Summary) .....	2
1.3.1 Architectural drawings – Annexure B .....	2
1.3.2 Engineering drawings and Specifications .....	3
1.3.3 Geotechnical Investigation – Annexure C.....	3
<b>2 FORENSIC INVESTIGATION</b> .....	3
2.1 Site Topographical Survey and Site Slope .....	3
2.2 Condition Assessment of the building .....	3
2.3 Areas of Investigation .....	4
2.3.1 Stormwater .....	4
2.3.2 External walls, Internal walls, roof and surface beds .....	4
<b>3 ENGINEERING REMEDIAL SOLUTIONS AND RECOMMENDATIONS</b> .....	5
3.1 Remedial A: Foundation strengthening .....	5
3.2 Remedial B: Stormwater Management .....	5
3.3 Remedial C: Crack repair – Expanded metal lath .....	6
<b>4 DESIGN PARAMETERS</b> .....	6
4.1 Design Standards, Regulations and Guidelines .....	6
4.2 Design Working Life .....	6
4.3 <b>Design Loads</b> .....	7
4.3.1 Dead Loads (Permanent Actions) .....	7
4.3.2 Wind Loads (Variable Actions) .....	7
4.3.3 Soil Loads.....	7
4.3.4 Seismic Loads .....	7
4.4 <b>Design Load Combinations</b> .....	7
4.4.1 Ultimate Limit State .....	7
4.5 <b>Materials</b> .....	7
4.5.1 Concrete and Reinforcement .....	7
4.5.2 Masonry works.....	8
4.6 Limiting Factors .....	8
<b>5 POSSIBLE ROUTE CAUSES OF DAMAGE AND CONCEPT PROPOSALS FOR REMEDIAL WORKS</b> .....	8
<b>6 RISKS &amp; MITIGATION MEASURES</b> .....	8

## Annexures

- A - Investigation (April 2024): Drawings
- Drawing No. House Bernard – Struct 01: Investigation and Structural remedial concepts
- B - Architect drawings – May 2020 (Rudman & Visagie)
- C - Geotechnical report - March 2024 (Dwala Group)

## EXECUTIVE SUMMARY

This **Forensic Investigation and Structural Engineering Remedial Concept Report** is presented by **TechQ Development Pty (Ltd)** based on the *Request for Proposals (RFP)* called by the **National Home Builders Registration Council (NHBRC)** in terms of the *Housing Consumer Protection Measures Act (Act 95 of 1998) and Regulations (HCPMA)*, and the *NHBRC Technical Requirements at Erf 18471, Mossel Bay (House Bernard)*, Western Cape Province. This property forms part of the “**Seemeeu Heights**” development. A design review discussion session was held with the NHBRC on 22 April 2024, with relevant comments incorporated in this report.

The objective of the structural remedial concepts proposed within this report is towards a safe retaining structure and adequate stormwater management. Details on the investigation and structural engineering remedial concepts are provided on the drawings in **Annexure A**.

Documentation made available to **TechQ** included the municipal approved Architect's drawing and Geotechnical investigation, all noted in **Section 1.3**.

**Section 2.2** of this report provides detail on the condition assessment of the structure and overall site properties, which portrays a sound building.

The concepts outlined in **Section 3** of this report are based on site inspections and the assessment done towards the complaints recorded by the Home Owner as record in the RFQ.

In summary, the following options are presented.

Section	Concept Remedial Actions
• <b>Foundations, walls and Stormwater</b>	<b><u>REMEDIAL A: Foundation Strengthening</u></b> <ul style="list-style-type: none"><li>• Concrete underpinning to foundations to large section of the house external footprint where settlement of foundations and structural cracks are evident.</li></ul>
	<b><u>REMEDIAL B: Stormwater Management</u></b> <ul style="list-style-type: none"><li>• Construct concrete aprons with open stormwater drainage channels.</li><li>• Repair paving where necessary.</li><li>• Install sub-soil drainage on eastern boundary of property</li></ul>
	<b><u>REMEDIAL C: Crack Repair</u></b> <ul style="list-style-type: none"><li>• Repair all mayor and small structural cracks emanating from settlement of foundations and lateral movement of walls.</li></ul>


---- End of Executive Summary ----

## 1 PROJECT LOCALITY, SCOPE AND INFORMATION

### 1.1 Project Locality

**Erf 18471, Mossel Bay (House Bernard)** is located at No.15, Seemeeu Heights, Mossel Bay within the boundaries of the **Mossel Bay Municipality** as show on the Figures below.

Site coordinates are **South:** 34° 08' 17" **East:** 22° 05' 27"



**Project Location: House Bernard – Seemeeu Heights**

### 1.2 Scope of Work

**TechQ Development (Pty) Ltd** was appointed by the **NHBC** to conduct a **Structural Investigation** towards the existing retaining wall at the back of the property with the following specific deliverables.

- Investigate defects that have manifested at the above-mentioned home and classify them in terms of the Housing Consumer Protection Measures Act (Act 95 of 1998) and Regulations (HCPMA) and the NHBC Technical Requirements.
- Determine the root causes of defects, report on the deformation of the existing structure and provide remedial solutions and specifications including drawings where necessary, towards the following areas as per previous reports filed by the **NHBC**:
  - Structural cracks on the external walls and internal walls

Throughout the investigation and considerations of remedial works, special attention is drawn to **Chapter III** of the Act, clause 13(1)(b) – (i) “rectify major structural defects” and (ii) “deviation from plans or any deficiency related to design, workmanship or materials”.

### 1.3 Information Provided (Summary)

Information provided by the NHBC, Home Owner and Engineering Service providers provided background to the site development and an understanding to analyse the structural system of the retaining wall in question and present concept structural proposals.

#### 1.3.1 Architectural drawings – Annexure B

Municipal approved architect drawings dated May 2020 (**Rudman & Visagie Architecture**) provided information on the layout of the property and building elements.

The owner reported that they are the 2<sup>nd</sup> owner of the property and cracks have been developing fast the past few months, which were not present at the time of purchase.

### 1.3.2 Engineering drawings and Specifications

No structural engineering drawings providing details on the external or internal walls and associated stormwater or sub-soil drainage were made available during the investigation.

### 1.3.3 Geotechnical Investigation – Annexure C

The geotechnical investigations conducted on **erf 18471** by **Dwala Group** in March 2024 are summarised below.

- The site is underlain with residual siltstone with a high (45%) liquid limit and PI of 12%.
- Shallow seepage and groundwater is detected.
- Foundation materials comprises of soils with a 41% compressibility and 59% collapsible character.
- Site slope invites erosion and promotes surface runoff.
- Foundation strip footings constructed directly on compressible and high potential collapsible material.
- Foundations are not adequate and no proper engineering fill was used to prevent settlements of the foundations.
- Water ingress between paving bricks directly onto foundations.
- Poor installation of subsoil drains on eastern boundary.
- House is under structural distress with both horizontal and vertical cracks because of compression and differential settlement.

Two (2) test pits were prepared by **DWALA Group** at strategic positions around the building with images and short descriptions given below.



**Test Pits:**

Foundations constructed on silty material



**Rainwater downpies**

Water ingress into paving



**Sub-soil drain on eastern boundary**

Non-operational sub-soil drain

The Dwala Group report recommends underpinning to foundations and installation of proper stormwater management systems.

## 2 FORENSIC INVESTIGATION

### 2.1 Site Topographical Survey and Site Slope

No site survey information was made available during the forensic investigation, however, indicative contour levels were detected from the Architect's drawing indicating a 1,5m slope from south to north over the site extend.

This slope necessitates proper stormwater and sub-soil drainage to protect the foundations and adequately drain stormwater.

### 2.2 Condition Assessment of the building


The table below and guided descriptions were used with the assessment and recommendations towards remedial works in securing a safe building

**Table 1: Condition Assessment Ratings**

Rating	Action required	Description
5 Very Good	Planned and Preventative Maintenance	New element or has recently been maintained, does not exhibit any signs of deterioration, and satisfies engineering specifications.
4 Good	Condition-based Maintenance	Superficial wear and tear, minor defects, minor signs of deterioration to elements and materials and requires routine maintenance / servicing.
3 Fair	Repairs needed	Require repair, usually by a specialist due to abnormal use or abuse and is in poor state of repair to affect surrounding elements.
2 Bad	Rehabilitation	Deterioration is bad, suffered structural damage and requires renovations. Serious potential of imminent failure which will lead to potential health and safety risk.
1 Very Bad	Structural rectifications/ Replacement	Element has failed its operational functions to the extent that does not justify repairs and needs to be replaced. The condition actively contributes to degradation of safety, health and risks.

The structural condition assessment of the building portrays a very high risk of failure towards the structural integrity of almost the entire building as schematically shown below.

**Figure 2: Condition Assessment**



The condition of the external walls are not as bad as the internal walls however, large cracks are evident over door and window openings on the perimeter of the building vertical walls.

## 2.3 Areas of Investigation

### 2.3.1 Stormwater

Segmented paving covers more than 80% of the property, however, water ingress is visible between the paving bricks due to settlement in the earth layer works. Numerous rainwater downpipes are also contributing to standing water on the surface in the absence of proper stormwater management.

As recorded in Section 1.3.3 above, a sub-soil drain was installed on the eastern boundary of the site, however not fully functional.

### 2.3.2 External walls, Internal walls, roof and surface beds

Settlement of pavement layers and ultimately the building foundation has resulted in medium to large cracks on both external and internal walls. Settlement of the building to the east has caused roof trussed to come loose from the brickworks.

Evidence of structural fatigue is noted at the kitchen window where a large crack divides all adjoining walls and pulls the wooden trusses from the external walls.

Possible underground heave soils are apparent from the large crack on the kitchen floor.




### 3 ENGINEERING REMEDIAL SOLUTIONS AND RECOMMENDATIONS

**Contributing factors** towards the **possible route causes** resulting in the large cracks forming on the external and internal walls are elaborated on in **Section 2.3** above.

Engineering remedial concepts are categorised and described below with full details on the drawings attached as **Annexure A**.


#### 3.1 Remedial A: Foundation strengthening

From the geotech report it is evident that no provision for engineering fill under foundations were done during construction. To stabilise the settlement, concrete underpinning is recommended to a large section of the external walls of the building as indicated on the drawings in **Annexure A** with graphical images below.



#### 3.2 Remedial B: Stormwater Management


Apart from concrete aprons around the building perimeter, a proper sub-soil drain and open channel stormwater system is proposed to adequately drain run-off water away from the structure. Below is proposed concepts with detail on the attached drawing.



**NOTE:** Cognisance must be taken of the wooden garden hut at the southern elevation and two (2) sets of stoep / stairs on the eastern elevation of the building to be removed and replaced after the underpinning and aprons have been constructed.

### 3.3 Remedial C: Crack repair – Expanded metal lath

Expanded metal lath application repairs to low- and high-level cracks as detailed on the drawing as per the image below.



## 4 DESIGN PARAMETERS

The following section of the **Report** is towards Quality Assurance and Continuous Professional Development to ensure due diligence of **TechQ Development's** approach to engineering solutions and problem solving in following the statutory design standards, regulations and guidelines.

### 4.1 Design Standards, Regulations and Guidelines

The design of structural elements, additions to, maintenance and/or repair remedial measures of affected *structural engineering elements* for this Project, is in accordance with the guidelines as set out in the latest version of the following South African design standards (SANS) and the National Building Regulations (NBR).

- SANS 10400 – Parts H, J, K, L, M & P - Masonry building design
- SANS 10100 - Part 1 - Concrete Design
- SANS 10144 - Detailing of steel reinforcement for concrete
- SANS 0161 / SANS 10400 – Part H - Foundation Design
- SANS 10130-2 - Self-weight and imposed loads
- SANS 1200 - Standardised specifications for construction works

### 4.2 Design Working Life

All structural elements shall be so designed to have a 50-year lifespan: **SANS 10160-1, Table 1.**

Design working life category	Indicative design working life - years	Description of structures
3	50	Building structures and other common structures

### 4.3 Design Loads

#### 4.3.1 Dead Loads (Permanent Actions)

**SANS 10160-1** read in conjunction with the requirements of **SANS 10160-2** for self-weight and imposed loads is applicable to the following elements.

Load Imposed on	Cause of Load	Load Value
Slab	Screed & tiles	1,2 kN/m <sup>2</sup>
Slab	110mm Brick walls	19,0 kN/m <sup>3</sup>

#### 4.3.2 Wind Loads (Variable Actions)

The following inputs are applicable in accordance with **SANS 10160-3** to calculate the peak wind speed pressure:

- Basic wind speed : 40 m/s
- Terrain Category : C (Regular cover of buildings, sub-urban terrain)
- Site Altitude : ± 25,0 MSL

#### 4.3.3 Soil Loads

**SANS 10160-1** read in conjunction with the requirements of **SANS 10160-5** will be applied.

#### 4.3.4 Seismic Loads

The Project Site does not fall within either **Zone I or Zone II** and no specific seismic design requirements are needed.

### 4.4 Design Load Combinations

#### 4.4.1 Ultimate Limit State

Ultimate limit state relates to the safety of the people and the structure. **SANS 10160-01** with reference according to **Table 3** outlines the Partial factors for actions for the ultimate limit state.

Dominating Action	Combination Name	Combination Equation
Self-weight	STR-P	1.35D + 1L
Imposed	STR	1.2D + 1.6L
Wind down	STR	1.2D + 1.3W↓ + 1.6ΨL
Wind up	STR	0.9D + 1.3W↑

### 4.5 Materials

#### 4.5.1 Concrete and Reinforcement

The following key structural materials and specifications are proposed for the remedial Works.

##### a. Concrete

All reinforced concrete elements shall be designed in accordance with **SANS 0100-1**. The 28-day characteristic strength of all concrete elements is to be as per the table below.

Structural Elements	Concrete Grade	Stone size
Foundations, Column bases and stub-columns	30 MPa	19 mm
Surface beds	25 MPa	19 mm
Aprons and Ramps	25 MPa	13 mm

b. Reinforcement

- Mild steel or R-Bars  $f_y = 250$  MPa minimum (to SANS 920)
- High yield or Y-Bars  $f_y = 450$  MPa minimum (to SANS 920)
- Welded steel mesh  $f_y = 485$  MPa minimum (to SANS 1024)

Bending schedules for the rebar to the concrete underpinning are detailed on the drawings and attached as **Annexure G**.

**4.5.2 Masonry works**

Where so detailed, specified and indicated on the drawings, typical **Type 2** (min) engineering bricks are to be used giving an **85mm** course height. All brickwork shall be set out in accordance with the relevant drawing layouts. Loadbearing brickwork should have a minimum crushing strength of **7MPa** with maximum 10% water absorption and **Class II** mortar.

**4.6 Limiting Factors**

Remedial and construction works as specified here within and detailed on the drawings, will require a **strategic phased decanting program** to be implemented during construction, drawn up in co-operation with the Home Owners. The safety of the Home Owners and the building need to be paramount, with construction works limiting the disruption of day-to-day and personal activities.

**5 POSSIBLE ROUTE CAUSES OF DAMAGE AND CONCEPT PROPOSALS FOR REMEDIAL WORKS**

**Contributing factors** towards the **possible route causes** resulting in the retaining wall to collapse can be some or a combination of the following.

- No engineering details towards proper measures in preventing settlement of underline soil materials or stabilisation of soils for foundations.
- Absence of proper stormwater features such as channels and sub-soil drainage.

The table below presents a summary to the forensic investigation and proposed concept options.

Section	Concept Remedial Actions
<ul style="list-style-type: none"> <li>• <b>Foundations, walls and Stormwater</b></li> </ul>	<p><b>REMEDIAL A: Foundation Strengthening</b></p> <ul style="list-style-type: none"> <li>• Concrete underpinning to foundations to large section of the house external footprint where settlement of foundations and structural cracks are evident.</li> </ul>
	<p><b>REMEDIAL B: Stormwater Management</b></p> <ul style="list-style-type: none"> <li>• Construct concrete aprons with open stormwater drainage channels.</li> <li>• Repair paving where necessary.</li> <li>• Install sub-soil drainage on eastern boundary of property</li> </ul>
	<p><b>REMEDIAL C: Crack Repair</b></p> <ul style="list-style-type: none"> <li>• Repair all mayor and small structural cracks emanating from settlement of foundations and lateral movement of walls.</li> </ul>

**6 RISKS & MITIGATION MEASURES**


Qualifications, risks and possible sensitivity issues needs to be considered in performing the proposed remedial Works during the construction stage. The main objective of the Project is repair works to the structural deformation of the building, however, the following aspects with mitigation proposals, need to be taken into consideration in the Risk Register of the Project.

## Risks and mitigation measures


Nature of Risk	Risk	Mitigation
Site and Construction Risks	Abnormal rainfall and restricted working space	Proper scheduling of Works, being aware of the "critical path" items and implementing effective construction methodologies, Quality Assurance and Controls.
Limiting Factors	Decanting plan	Phased implementation of Works in accordance with proper planned decanting program.
Health and Safety	Delays and Fatal	Detailed OH&S plan compiled.
Quality Assurance	Construction Management	QA and QC Inspection procedures in place and approved
	Sub-standard materials	Quality tests and Agreements in place
OH&S and Environmental	Disturbance to environment, community and workers	Focus on the environment, building rubble disposals, air and noise pollution and disruption of day-to-day operations

--- End of Report ---

PROJECT SCOPE and INVESTIGATIVE NOTES




GROUND FLOOR LAYOUT  
Site / Building layout and Area of Investigation




POSSIBLE ROUTE CAUSES OF DEFECTS and REMEDIAL CONCEPTS


REMEDIAL A: FOUNDATION STRENGTHENING - Concrete underpinning



FOUNDATION STRENGTHENING  
Concrete underpinning




SECTION A - A  
Concrete Underpinning




SECTION B - B  
Apron and open channel


REMEDIAL B: STORMWATER MANAGEMENT - Apron and channel




STORMWATER MANAGEMENT  
Concrete apron, open channel and sub-soil drain




DETAIL No.1  
Storm water drainage



SECTION C - C  
Apron, open channel and sub-soil drain




PRECAST STORMWATER CHANNEL  
Type - D6



DETAIL No.2  
Sub-soil drain

REMEDIAL C: CRACK REPAIR - Metal Lath



CRACK REPAIR  
Above and under Windows

CRACK REPAIR  
Above doors and Openings

CRACK REPAIR : EXPANDED METAL LATH  
Procedures

1. Verify affected areas with the Engineer and remove plaster with light hand tools.
2. Light chisel opening - 5mm deep of apparent crack.
3. Fix galvanise lath mesh to area with galv. nails, 300mm max centers.
4. Lath metal tightly stretched to reduce waviness.
5. Plaster forced through openings of mesh so the lath is completely encased in the plaster (1:5 mix).
6. Repaint to match existing.

**NOTES:**

1. This drawing to be read in conjunction with the following documents:  
Forensic Report - 26 April 2024
2. No dimensions may be scaled from this drawing.
3. Special care to be taken during all construction operations to not damage or disconnect any services (water, sewer and electrical).

CLIENT  
NATIONAL HOME BUILDERS  
**NHBRC**  
REGISTRATION COUNCIL  
Centennial Place  
East Block  
Century City Boulevard  
Milnerfontein

Tel: (021) 913 9210  
Call: (083) 475 3546  
e-mail: dailson@nhbrc.org.za

PROJECT TITLE  
Structural Engineering Services for  
Erif 18471, Mossel Bay  
(House Bernard)

DRAWING TITLE  
Structural Investigation, Possible causes  
and Proposed Remedial Works

Revisions		
Date	No.	Description

Reference Drawings	
Dwg Number	Description

Drawing Issued for / as:

- Structural investigation
- Design
- Construction
- As-built

Office Corner, Block C  
184 Lancaster Road  
Gordon's Bay  
7140

Tel: (0664) 105 1226  
Fax: (086) 474 1937  
e-mail: techq.development@outlook.com

DATE	DRAWN	SCALE	MAINTENANCE	CHECKED	YES
April 2024	MJB	AS-SHOWN		MJB	

Stand Nr. and locality:  
**ERF 18471, Mossel Bay  
Vyf Brakke Fonteynen**

ENGINEERING DESIGNS - Structural & Civil services

Designed by: M.J. Badenhorst	Drawn: MJB	Checked: MJB
---------------------------------	---------------	-----------------

Competent Person:  
M.J. Badenhorst (Pr.Tech.Eng)  
ECSA # 200270009  
NHBRC Code # 601551

Cell: 066 105 1226  
meltbadenhorst@outlook.com

Drawing number:  
House Bernard - Struct 01


Signature:  
*M.J. Badenhorst*

Drawing size: A1	Rev: 00
---------------------	------------


Client Approval:  
Signature:




Iigging nvs




SNIT A-A 1:100




SNIT B-B 1:100




NOORDAANSIG




SUIDAANSIG



OOSAANSIG



WESAANSIG



TERREINPLAN 1:100

Nuwe tuin skaar 6m<sup>2</sup>

- GENERAL NOTES**
1. ALL WORK TO COMPLY WITH LOCAL AUTHORITIES REQUIREMENTS (1977) AND ESCOM WIRING REGULATIONS (1971 No. 19) OF 1972.
  2. ALL THE DIMENSIONS ON THE PLAN ARE TO BE CHECKED BEFORE COMMENCEMENT OF WORK.
  3. WRITTEN DIMENSIONS TO TAKE PRECEDENCE TO SCALING FROM DRAWINGS.
  4. DRAWINGS TO BE READ IN CONJUNCTION WITH PLANS AND SECTIONS.
  5. ALL GROUND LEVELS TO BE CHECKED ON SITE PRIOR TO ANY WORK. GROUND LEVELS ON PLAN ARE ONLY FOR INDICATION.
  6. 25mm BACKGROUND TO BE USED IN ALL WALLS EVERY FOURTH COURSE AND EVERY COURSE FOR FOUR LAYERS ABOVE ALL ABOVE AND DOOR, WHILE AT THE EVERY FOURTH COURSE.
  7. 375 MICRON BRICKS/CLAY DAMP-PROOF COURSE, MUST BE USED (SEE NOTES D).

**BELEGTING Make 5W/K<sup>2</sup>m**

**140.40 x 5 = 702W**

**TOTAL = 480W**

12. BRINE LITE @ 30W / LIC = 120W  
4. BRINE LITE @ 30W / LIC = 120W

**SEEMEEU HOOGTE**

Hoogte van die oppervlakte van die grondvlak van die gebou tot die hoogste punt van die dak.

Hoogte van die oppervlakte van die grondvlak van die gebou tot die hoogste punt van die dak.

Hoogte van die oppervlakte van die grondvlak van die gebou tot die hoogste punt van die dak.

**VOORGESTELDE AREAS**

MAGER AREA	:- 112,85 K <sup>2</sup> m
MOTORHUIS	:- 23,45 K <sup>2</sup> m
ONDERDAK STOEI	:- 4,00 K <sup>2</sup> m
<b>TOTAL</b>	<b>:- 140,30 K<sup>2</sup>m</b>
DEKING	= 36 %

**ELECTRICAL LEGEND**

☐	OSTV	☐	PREPARED METER
☐	ALARM SENSOR	☐	UNDER FLOOR HEATING CONTROL
☐	UNDER FLOOR HEATING	☐	DIMMER
☐	CEILING LIGHT FITTING	☐	OUTSIDE LIGHT FITTING
☐	12 V DOWNLIGHTER	☐	SPEAKERS
☐	SHAVING POINT	☐	SMOKING POINT
☐	SINGLE 15 AMP PLUG 300 F.F.L.	☐	DOUBLE 15 AMP PLUG 300 F.F.L.
☐	DOUBLE 15 AMP PLUG 1200 F.F.L.	☐	TELEPHONE POINT
☐	FAX POINT	☐	SWITCHBOARD
☐	200 LL GETSER IN ROOF SPACE	☐	DOOR BELL AND CHIME
☐	TV POINT		

**Rudman & Visagie**  
Rudman & Visagie  
1989

**BUILDING CONSULTANTS**

P.O. BOX 2420  
MOSSEL BAY  
65000  
TEL: 044 - 8111993  
FAX: 044 - 8111993  
Info@rudmanvisagie.co.za

**DRAWING TITLE: WYSGESTEKENING (soos gebou)**

PROJECT TITLE: WYSGINGS AAN BEST. WONING

STAND No.: 1 8 4 7 1

TOWNSHIP: SEEMEEU HOOGTE N- 15

MUNICIPALITY: MOSSELBAAI

FOR OWNER: Mnr J.S. TAIT

OWNER'S SIGNATURE: [Signature]

SCALE: 1:100 & 1:200

CREATED BY: MVS

CAD NAME & No.: C: Morris

DATE: FEB 2020

**REVISION NO.**

A	B	C

DESTROY ALL PREVIOUS PRINTS © COPYRIGHT RESERVED.

**APPROVED FOR APPROVAL TO BE SUBMITTED TO THE ARCHITECTURAL PROFESSION REG. NO. 10227 - MARAS VISAGE**

DATE: 11 MAY 2020

SCANNED

# GEOTECHNICAL INVESTIGATION FOR 15 SEEMEEU HOOGTE, MOSSEL BAY

## HOUSE BERNARD



Prepared By:



Prepared For:





Document prepared by:

Dwala Group Pty Ltd

2014/223042/07

F +27 86 552 2337

E nhlanhla@dwalagroup.com

W dwalagroup.com

A person using Dwala Group documents or data accepts the risk of:

- a) Using the documents or data in electronic form without requesting and checking them for accuracy against the original hard copy version.
- b) Using the documents or data for any purpose not agreed to in writing by Dwala Group.

Document control			
<b>Report title</b>	Geotechnical report for the proposed remedial works for a deforming house (House Bernard).		
<b>Client</b>	National Home Builders Registration Council (NHBRC)		
<b>Date</b>	24 March 2024	<b>Keywords</b>	
<b>Compiled by:</b>	Lethabo Moatshe	Residual material	Strip footing
<b>Checked by:</b>	Sboniso Zondi	Cracks	Compressible soil
<b>Approved by:</b>	Nhlanhla Magigaba	Concrete apron	Drainage measures
Rev		00	

# Contents

<b>EXECUTIVE SUMMARY</b>	<b>i</b>
<b>1. Introduction</b>	<b>1</b>
<b>2. Available information</b>	<b>1</b>
<b>3. Site locality and description</b>	<b>2</b>
<b>4. Climate</b>	<b>3</b>
<b>5. Geology</b>	<b>4</b>
<b>6. Investigation Methodology</b>	<b>5</b>
6.1 Test pitting	5
6.2 Laboratory testing	5
<b>7. Results of Investigation</b>	<b>6</b>
7.1 Fill horizon	6
Residual Siltstone Horizon	7
<b>8. Groundwater conditions</b>	<b>7</b>
<b>9. Laboratory tests</b>	<b>7</b>
9.1 Foundation Indicators	7
<b>10. Geotechnical Considerations</b>	<b>8</b>
10.1 Shallow seepage/groundwater level	8
10.2 Compressible Soil Profile	8
10.3 Collapsible soil profile	8
10.4 Erodibility of the soil profile (present)	9
<b>11. Current Site Conditions</b>	<b>9</b>
11.1 Foundation conditions	9
11.2 Drainage Measures	9
11.3 Concrete Apron	11
11.4 Structural conditions	11
<b>12. Engineering Geological Zoning</b>	<b>15</b>
<b>13. Conclusions</b>	<b>16</b>
<b>14. Recommendations</b>	<b>16</b>
14.1 Foundations	17
14.2 Soil Moisture Stabilisation	17
14.3 Professional Indemnity	17
<b>15. References</b>	<b>18</b>

# Appendices

## Appendix A

Summary of Standard Soil and Rock Profile Description Terminology

## Appendix B

Soil Profile Descriptions

## Appendix C

Laboratory Test Results

## Appendix D

Settlement Calculations

## Appendix E

Site Plan

## Figures

Figure 1: Showing the investigated house in Vyf Brakke Fonteynen, Mossel Bay (blue outline).	2
Figure 2: Showing the topography of the site and the brick pavement around the house.	3
Figure 3: Showing the garden area on the property.	3
Figure 4: Showing the general geology map of the site; (Geological Survey, printed by the Government Printer, Pretoria, 1979).	4
Figure 5: Showing test pit HB1.	6
Figure 6: Showing the gutters around the investigated house.	10
Figure 7: Showing the stormwater pipe in the garden area.	10
Figure 8: Showing the inadequate brick pavement with spaces between bricks around the house.	11
Figure 9: Showing the horizontal, diagonal, and vertical cracks on the interior walls of the investigated house.	12
Figure 10: Showing the cracks on the exterior walls around the investigated house.	13
Figure 11: Showing the settlement in pavement and garden area.	14

## Tables

Table 1: Test pit summary	5
Table 2: Test pit profile summary	6
Table 3: Summary of Foundation Indicator test results	7
Table 4: Geotechnical Characteristics	15

## EXECUTIVE SUMMARY

NHBRC appointed Dwala Group to carry out a geotechnical investigation for a deforming structure (House Bernard). The study area is situated at 15 Seemeeu Hoogte in Vyf Brakke Fonteynen, Mossel Bay, in the Western Cape Province. The geotechnical investigation comprised of desktop study, fieldwork (test pit excavation, soil profiling, and sampling of selected horizon for laboratory testing), laboratory testing and reporting.

The main objective of the investigation was to investigate the cause of the deformation in the existing structure, evaluate the founding conditions, and give recommendations for remedial actions.

The geological profile revealed that the site is underlain by fill and residual siltstone material.

According to the geotechnical characteristics of the soil material encountered under the foundations, the investigated site is zoned as Zone C2. This zone covers the entire site and is characterized by the compressible, and potentially collapsible residual siltstone horizon (silty sands, clayey sand material). The expected total settlement for this zone is greater than 10 mm and a differential movement that is 75%.

**It was observed during the investigations that the strip footings are placed directly on the compressible, and potentially collapsible material, as such, no measures were put in place to prevent differential settlement of residual siltstone materials on site.**

Based on the soil profile characteristics and the condition of the structure, it is evident that the structure should have been founded either on a foundation of substantial stiffness if it had to perform satisfactorily. This would have required a soil raft of non-active material placed on a concrete raft foundation with high stiffness. This solution would typically be combined with limited articulation and a substantial brick force specification.

Due to the fact that the foundation materials below the foundation are compressible and potentially collapsible, the underpinning of the foundation is considered suitable for strengthening the foundation.

**Measures to attempt to stabilise future soil moisture change and hence curb further movement as effectively as possible must be implemented.**

## 1. Introduction

NHBRC appointed Dwala Group to carry out a geotechnical investigation for a deforming structure (House Bernard). The study area is situated at 15 Seemeeu Hoogte, Vyf Brakke Fonteynen in Mossel Bay, Western Cape Province. Fieldwork carried out on the 21<sup>st</sup> of February 2024, included excavation of test pits, soil profiling, soil sampling, and exposing existing foundations of the structure to assess the possible factors that might be causing the house to deform (crack).

The objectives of the geotechnical investigation were to:

- Present a discussion on the prevailing condition of the structure.
- Determine the stratigraphy of the site and its geotechnical properties.
- To determine whether any problem soils are present at the site that could have had an effect on either founding or construction methods for the structure to deform (crack).
- To delineate the site into appropriate geotechnical zones according to any essential differences in founding conditions encountered.
- To evaluate the founding conditions at the site and to recommend building precautions necessary for different geotechnical zones.
- To obtain basic data concerning the use of the in-situ materials for guideline purposes.
- To present findings and recommend measures to restrict or reduce further structural distress in the structure.

The approach to the investigation was to assess the status quo in terms of the characteristics of the soil profile and the measures implemented (if any) to protect the structure against potential differential movements. This is followed by recommendations on appropriate rectification measures.

## 2. Available information

At the time of the investigation, the following information was available:

- The 1:250 000 scale geological map of the Oudtshoorn Sheet 3322 (Council for Geosciences, 1979).
- Aerial photographs, sourced from Google Earth®.

### 3. Site locality and description

The investigated site is situated at 15 Seemeeu Hoogte in Vyf Brakke Fonteynen, Mossel Bay, in the Western Cape Province. The site is located approximately 12 km northwest of Mossel Bay Central. The property can be accessed from R102, onto Boekenhout Avenue, onto Kameeldoring Avenue, onto Wassenaar Street, and Rylaan 5 into Seemeeu Hoogte. The area consists of residential developments. Figure 1 below shows the site locality of the investigated house.




Figure 1: Showing the investigated house in Vyf Brakke Fonteynen, Mossel Bay (blue outline).

Topographically the property moderately slopes at an angle of approximately  $6^\circ$  towards the north-easterly direction.

The investigated house is covered by pavement all around the house as shown in Figure 2 below and grass and decorative stones on the northeast side of the house as shown in Figure 3 below.



Figure 2: Showing the topography of the site and the brick pavement around the house.



Figure 3: Showing the garden area on the property.

## 4. Climate

The climate in Mossel Bay is warm and temperate. The climate of the area is classified as Cfb by the Köppen-Geiger system. The temperature here averages 17.0°C. Mossel Bay has a lot of rainfall; even in the driest months, averaging 36 mm in February. In November, the precipitation reaches its peak, with an average of 56 mm. The rainfall is approximately 538 mm annually (Climate-data.org: 2012).

The Weinert Climatic N-number for the area (Weinert, 1980) is <5, which indicates that the climate is semi-humid to humid and chemical weathering processes are dominant.

## 5. Geology

According to a 1:250 000 scale geological map of the Oudtshoorn sheet 3322 (Council for Geoscience, 1979), the investigated site is underlain by conglomerate, sandstone, siltstone and clay of the Cretaceous to Tertiary Era. This lithology was confirmed in the test pits excavated on site. Figure 4 below shows the geological map of the investigated area.




Figure 4: Showing the general geology map of the site; (Geological Survey, printed by the Government Printer, Pretoria, 1979).



## 6. Investigation Methodology

The geotechnical investigation comprised desktop study, fieldwork, laboratory testing and analysis and reporting.

### 6.1 Test pitting

To meet the requirements for a stand to be registered with NHBC the investigation was carried out in accordance with the specification for geotechnical site investigations for housing developments (National Department of Housing specification GFSH- 2).

Fieldwork included excavation and profiling of two (2 No.) test pits excavated. One (1 No.) test pit was excavated next to the building to expose the foundations to have a clear understanding of the materials under the foundations. The other test pit was excavated to assess the stormwater drain on the northeast side of the house. To expose the foundation, the test pit was excavated to a depth of 1.50 m or to refusal on hard material.

A two-person team carried out the test pitting in order to comply with accepted safety requirements as reflected in the Site Investigation Code of Practice (SAICE, 2010). The test pits were set out and profiled by a team of engineering geologists/ geotechnical engineers in accordance with South African standards (*Jennings, J E B, Brink, A B A and Williams, A A B, (1973). Revised Guide to Soil Profiling for Civil Engineering Purposes in Southern Africa. The Civil Engineer in S A, p 3-12. January 1973.*). Test pit details are summarised in Table 1 below.

Table 1: Test pit summary

Test Pit No	Coordinates (WGS84)		Depth (m)	Remarks
	Latitude	Longitude		
HB1	34° 8'17.09"S	22° 5'27.07"E	1.1 m	Refusal on dense residual siltstone
HB2	34° 8'16.88"S	22° 5'27.47"E	1.3 m	No Refusal

### 6.2 Laboratory testing

Representative samples were recovered and submitted to the SANAS-accredited Engineering Laboratory in George for testing. Soil testing included the determination of the Foundation Indicators (comprising sieve and hydrometer grading analyses and Atterberg Limits) as well as the determination of in-situ moisture content.

## 7. Results of Investigation

The detailed descriptions of the soil profiles encountered in the test pits are presented in Appendix B, while the soil profiles for the whole site are summarised below in Table 2.

Table 2: Test pit profile summary

Test Pit No	Brick Wall	Concrete Foundation	Fill horizon	Residual Siltstone horizon
HB1	0 – 0.50	0.50 – 0.80		0.80 – 1.10
HB2	-	-	00 – 1.30	-

Figure 5 below shows the excavated test pit HB1 on-site. The profile on-site consists of fill and residual siltstone horizon.



Figure 5: Showing test pit HB1.

### 7.1 Fill horizon

The fill horizon was encountered in one (1 No.) test pit HB2 excavated on site. The horizon comprises moist, dark brown, speckled grey, sandy clay with sparse gravel and pebbles. The overall consistency of this horizon is soft to firm.

## Residual Siltstone Horizon

The residual siltstone horizon was encountered in one (1 No.) test pit HB1 excavated on site. The horizon comprises slightly moist to moist, olive green, dark reddish brown, mottled orangey, clayey sand with sparse gravel and pebbles. The overall consistency of this horizon is medium-dense.

## 8. Groundwater conditions

Groundwater seepage was not encountered in the test pits excavated on site.

## 9. Laboratory tests

Representative samples of the materials encountered on site were taken and submitted to a soil laboratory where they were subjected to the following tests:

- Grading and Atterberg Limits including moisture content.

The laboratory results are attached as Appendix C to this report.

### 9.1 Foundation Indicators

Representative samples were collected for laboratory testing and submitted for foundation indicator tests. The test results are attached in Appendix C and summarised in Table 3 below.

Table 3: Summary of Foundation Indicator test results

Hole no.	Depth ( m )	Soil composition				GM	Atterberg limits			Activity	Moisture Content	Unified soil classification
		Clay (%)	Silt (%)	Sand (%)	Gravel (%)		LL (%)	PI (%)	LS (%)			
<b>Residual Siltstone horizon</b>												
HB1	0.75 – 1.40	24.0	17.0	44.0	15.0	1.03	45.0	12.0	6.0	Low	32.9	SM

Where: GM = Grading modulus  
 LL = Liquid Limit  
 PI = Plasticity Index  
 LS = Linear Shrinkage  
 Activity = Expansiveness of the soil according to Van der Merwe's method  
 SM = Silty Sand

Table 3 above indicates that:

The **residual siltstone material** underlying the site consists of silty sand (**SM**) with a moisture content of 32.9%. The horizon has a high grading modulus of 1.03. The fine fractions of this material also exhibit moderate (45.0%) liquid limit as well as moderate (6.0%) linear shrinkage. The plasticity index (PI) of the material is moderate (12.0%). The material has a low potential expansiveness, according to the method proposed by Van der Merwe (1973).

## 10. Geotechnical Considerations

The following constraints, as proposed by Partridge, Wood, and Brink (1993), have to be considered for the classification of this site.

### 10.1 Shallow seepage/groundwater level

Groundwater seepage was not encountered in the test pits excavated on site.

However, at the time of the investigation, there was no effective moisture barrier around the house to protect the foundations and the soil under and around it from direct infiltration of water by draining them away to prevent foundation movement and structural damage. The underlying silty sand materials were encountered as very moist with a moisture content of 32.9% respectively, which indicates that water reaches the sub-foundation soils which is detrimental to the foundations and the structure of the house.

### 10.2 Compressible Soil Profile

The foundation indicator test results (see Section 9) indicate that the residual siltstone materials on-site comprise 41.0% fine-grained soils. Fine soils are prone to compressibility with changes in moisture content and additional load of the house.

The fine materials of the residual siltstone horizon where the foundations of the house are placed underwent compression and settlement when the moisture conditions under the foundations changed due to water permeating into the foundations and subsoil, seasonal rainfall, and the lack of a concrete apron around the house.

### 10.3 Collapsible soil profile

The foundation indicator test results (see Section 10) indicate that the residual siltstone horizon material on-site comprises 59.0% coarse-grained soils. Coarse-grained soils are prone to collapse upon wetting and additional loading.

The coarse materials of the residual siltstone material where the foundations of the investigated house are placed underwent collapse settlement when the moisture content increased in the subsoil under the foundations due to seasonal rainfall, and water draining directly into the soil and the foundations of the house as well as the additional load of the house.

## 10.4 Erodibility of the soil profile (present)

Due to the moderate slope of the area, erosion is occurring on the site as the slope promotes surface runoff. The residual siltstone materials at the site also consist of silt and fine sand materials which are prone to erodibility. Problems of erodibility exist on the site as water has infiltrated the foundations, and eroded the finer materials of the subsoil which has led to the collapse of the founding materials under the house. Surface runoff must be controlled on-site to protect the structures from further erosion of the surface and underlying founding materials.

It is recommended that surface drains be installed properly on the site to control surface water and drain water away from the foundations.

## 11. Current Site Conditions

### 11.1 Foundation conditions

Inspection of the foundations of the investigated house showed that the house is founded on “strip footings” with a thickness of 300 mm and a width of 960 mm. **The strip footings are placed directly on the compressible, and potentially collapsible material.**

The soil profile at the excavated test pit indicates that no proper measures (e.g. treatment/improvement of the compressible, and potentially collapsible soil profile and/or replacement of compressible material with a properly engineered fill) were put in place to prevent settlement.

Furthermore, the residual siltstone horizon on site was encountered as moist with a moisture content of 32.9%. These materials undergo compression when moisture conditions change from dry to moist. This is problematic since inter alia seasonal moisture changes from dry to very moist in the foundation and sub-foundation horizons of especially lightly loaded fixed structures give rise to volumetric changes. Volumetric change in the soil skeleton in turn induces stresses in the footings and super-structure, leading to super-structure strain and cracking.

**The foundations on site are considered to be inadequate to withstand the differential settlement that inevitably occurred due to the underlying compressible, and potentially collapsible materials; however, the structural engineer will confirm the suitability of the foundations.**

### 11.2 Drainage Measures

A proper drainage system prevents water from accumulating around a house, potentially causing damage to its structure and/or foundations.

The gutters around the house channel water **directly onto the inadequate paving and into the foundations and subsoil**. This allows for water to permeate the soil directly and infiltrate through to the foundations facilitating the movement of foundations and leading to structural damage. Figure 6 below shows the gutters around the house.



Figure 6: Showing the gutters around the investigated house.

Upon exposure of the stormwater drainage pipe in the garden area, there were no visible signs of damage or leakage or disconnect. The pipe was encountered to be at a depth of 300 mm and extend to 1.0 m below the ground. Sandy clay with minor gravel and pebbles was used as backfill for the pipe. While the stormwater drainage system appears without visible damage, it should be noted that it cannot be definitively affirmed that there are no leakages during periods of heavy rainfall. Figure 7 below shows the stormwater pipe in the garden area.



Figure 7: Showing the stormwater pipe in the garden area.

### 11.3 Concrete Apron

The function of a concrete apron around a building is to protect the foundations and the soil under and around it from water and prevent it from directly infiltrating into the foundations by draining them away to prevent foundation movement and structural damage.

The brick pavement around the house is inadequate as there are spaces between the building walls and the brick pavement. This renders the pavement ineffective in keeping surface runoff away from the subsoils and subsequently the foundations. It allowed water to permeate through the foundations and the residual siltstone material directly, increasing the moisture content in the sub-foundation horizon. There are also signs of stagnant water on the pavers which is not drained away. Figure 8 below shows the inadequate brick paving around the investigated house.



Figure 8: Showing the inadequate brick pavement with spaces between bricks around the house.

**The inadequate brick paving around the investigated house allowed water to permeate through to the foundations and directly into the foundations and subsoil residual siltstone material. These materials absorbed the water and induced plastic deformations of the soils. The change in moisture content of the subsoil and the load of the house has triggered the compression/collapse and consequently differential settlement of the subsoil and thus caused the movement of foundations resulting in structural damage to the house.**

### 11.4 Structural conditions

The house under assessment displayed structural distress (lateral and vertical movement) because of compression and ultimately differential settlement. Cracks were observed on the interior walls of the house extending from the ceiling, corners of the windows and doors, and on the floors and tiles inside the house as shown in Figure 9 below and on the exterior walls as shown below in Figure 10. It is worth noting that this site most likely experiencing compression that heave.




Figure 9: Showing the horizontal, diagonal, and vertical cracks on the interior walls of the investigated house.





Figure 10: Showing the cracks on the exterior walls around the investigated house.

The garden area and paving on the northeast side of the house has settled and a depression of the pavement is seen as shown in Figure 11 below.



Figure 11: Showing the settlement in pavement and garden area.

Based on the soil profile characteristics on the site and the condition of the structures, it is evident that the structures should have been founded either on a foundation of substantial stiffness if it had to perform satisfactorily. This would have required a soil raft of non-active material of about 1.50 m in thickness or a concrete raft foundation with high stiffness. These solutions would typically be combined with limited articulation and a substantial brick force specification.

## 12. Engineering Geological Zoning

For urban planning purposes, the site is zoned according to the NHBRC classification systems. Due to the presence of compressible, and potentially collapsible soil horizon under the entire site, the site has been delineated into one geotechnical zone. The descriptions of this zone are as follows:

**Zone C2:** This zone covers the entire site and is characterized by the compressible, and potentially collapsible residual siltstone horizon (silty sands, clayey sand material). The expected total settlement for this zone is greater than 10 mm and a differential movement that is 75% (**C2**).

Table 4: Geotechnical Characteristics

Geotechnical Characteristics				
Typical Founding Material	Character of Founding Material	Expected Range of Total Soil Movements (Mm)	Assumed Differential Movement (% of Total)	Site Class
Silty sands, sands, sandy and gravelly soils	Compressible and Potentially Collapsible Soils	<5,0	75%	C
		5,0-10,0	75%	C1
		<b>&gt;10,0</b>	<b>75%</b>	<b>C2</b>

The expected immediate total settlement of the foundations in test pit HB1 is **17.00 mm** on the residual siltstone material based on a founding depth of 0.80 m, a strip footing width of 0.96 m and an in-situ stiffness of 7 MPa (using the method proposed by Janbu et.al, 1956).

Settlement larger than 10 mm is likely to be differential and may compromise the structure of the development. It is therefore recommended that the clay be treated and strip footings be placed on engineered fill. When the in-situ clay is treated and engineered fill placed on top, the settlements can be expected to drop below 10 mm.

The allowable bearing capacity (FoS=3) of this material is approximately 89kPa.

## 13. Conclusions

The conclusion of the investigation can be summarised as follows:

- The diagonal, vertical and horizontal cracks around the building indicate movement of the foundations.
- The residual siltstone material comprises predominantly silty sand material.
- The laboratory tests indicate that the soil profile has low potential expansiveness, however, it is compressible, and potentially collapsible due to the silty and sandy nature of the materials.
- Settlement calculations show that upon the change in moisture content of the sub-foundation soils on site, the average settlement for the site is approximately **17.0 mm**.
- **The structural distress which is observed on this site can mainly be ascribed to the expected differential settlement of 13.0 mm, which is a result of compressible, and collapsible material below the founding level.**
- **The house has no effective moisture barrier/apron. Concentration and discharging of rainwater, directly onto the soil and via downpipes, against the structure have increased the risk of differential settlement.**
- A depression and settlement of the pavement are noted along the northeastern side of the house near the stormwater pipe.
- The stormwater drainage pipe shows no signs of damage, it cannot be definitively affirmed that there are no leakages during periods of heavy rainfall.
- Cracks smaller than 0.5 mm could have been caused by a combination of settlement and temperature differences. Other factors may have contributed, but it is difficult to determine (e.g. moisture content in masonry bricks).

## 14. Recommendations

Plans for the building have been obtained to study the footing details. However, for purposes of prescribing rectification measures and based on what we have seen first-hand and engineering drawings of the actual footings, this information is not critical:

The approach followed in the rectification process represents a dichotomy, viz:

- Underpinning;
- Incorporating measures to attempt stabilising future soil moisture change and hence curb heave/shrinkage movement as effectively as possible; and
- Protecting the structure against additional potential movement by strengthening the superstructure where necessary, but at the same time providing flexibility to it by way of movement joints (these recommendations will be done by a structural engineer).

## 14.1 Foundations

Due to the fact that the foundation material below the foundation is potentially collapsible and compressible, the **underpinning of the foundation should be considered and investigated**. There is a risk of cracking during the process and the shrinkage of the fresh concrete, but this will stabilize with time. It is also difficult to underpin the internal walls. Should the client select this option, the structural engineer can prepare a detailed procedure for the process.

## 14.2 Soil Moisture Stabilisation

**Water must be kept away from the foundations. To stabilise the soil moisture around the foundations of the house an adequate apron of approximately 1.50 m width must be constructed around the house in such a way that water does not pond anywhere directly next to the structure of the house.** This will require draping of the soil before placing the apron. **When carrying out the above it must be confirmed that no services are leaking.**

In addition, while a garden may be established near the buildings, no large trees should be planted near the buildings. Watering plants close to the house may have a negative effect on the moisture stabilisation below the foundation.

## 14.3 Professional Indemnity

Dwala Group has not carried out detailed construction supervision or design and therefore accepts no responsibility for the design and/or failures and consequences, therefore, that may occur in the future. We would, however, like to assist with recommendations for the repair of the structure.

The recommendations and methods of construction must be finalised with a contractor. It must be emphasised that all measures to render an existing structure crack free, is certainly more difficult to incorporate than in the case of a new structure still to be built. Although there is no guarantee against minor and isolated cracks developing subsequent to the implementation of these measures, a high success rate is possible, particularly to the extent of maintaining a high degree of aesthetical appeal.

## 15. References

1. Geological Survey (Council for Geoscience), 1979. 1:250 000 Geological Map Sheet #3322 Oudtshoorn.
2. Geotechnical Investigations for Housing Developments, Generic Specifications GFSH-2, September 2002.
3. <https://en.climate-data.org/africa/south-africa/western-cape/mossel-bay-914458/>  
[Accessed on 2 March 2024]
4. Jennings, J E B, Brink, A B A and Williams, A A B, (1973). Revised Guide to Soil Profiling for Civil Engineering Purposes in Southern Africa. The Civil Engineer in S A, p 3-12. January 1973.
5. National Home Builders Registration Council, Home Building Manual, Part 1 & 2. First revision, February 1999.
6. Partridge TC, Wood CK and Brink ABA “Priorities for urban expansion within the PWV metropolitan region: The primacy of geotechnical constraints”. South African Geographical Journal, Vol. 75, pp 9 – 13. . 1993.
7. South African National Standard. *Profiling, Percussion Borehole and Core Logging in Southern Africa*. SANS 633:2012.
8. Site Investigation Code of Practice, 1st Edition, South African Institution of Civil Engineering - Geotechnical Division, January, 2010.
9. South African Loading Code SANS 10160 Basis for structural design and actions for buildings and industrial structures – Part 4: Seismic actions and general requirements for buildings, 2011.
10. Wagner A.A., 1957, “The use of unified soils classification system by Bureau of Reclamation”, Proceedings of the 4th ICSMFE, London, Vol 1:125
11. Weinert, H.H. 1980. The Natural Road Construction Materials of Southern Africa. Academica. Pretoria.

# Appendix A

## Summary of Standard Soil and Rock Profile Description Terminology

## STANDARD DESCRIPTIONS USED IN SOIL PROFILING

1. MOISTURE CONDITION		2. COLOUR	
Term	Description	The Predominant colours or colour combinations are described including secondary coloration described as banded, streaked, blotched, mottled, speckled or stained.	
Dry			
Slightly moist	Requires addition of water to reach optimum moisture content for compaction		
Moist	Near optimum content		
Very Moist	Requires drying to attain optimum content		
Wet	Fully saturated and generally below the water table		
3. CONSISTENCY			
3.1 Non-Cohesive Soils		3.2 Cohesive Soils	
Term	Description	Term	Description
Very Loose	Crumbles very easily when scraped with geological pick	Very soft	Easily penetrated by thumb. Sharp end of the pick can be pushed in 30 - 40mm. Easily moulded by fingers.
Loose	Small resistance to penetration by the sharp end of the geological pick	Soft	The pick head can easily be pushed into the shaft of the handle. Moulded by fingers with some pressure.
Medium Dense	Considerable resistance to penetration by the sharp end of the geological pick	Firm	Indented by thumb with effort. Sharp end of the pick can be pushed in up to 10mm. Can just be penetrated with an ordinary spade.
Dense	Very high resistance to penetration to the sharp end of geological pick. Requires many blows of hand-pick for excavation.	Stiff	Penetrated by thumbnail. Slight indentation is produced by pushing the pick point into the soil. Cannot be moulded by fingers. Requires hand-pick for excavation.
Very Dense	High resistance to repeated blows of geological pick. Requires power tools for excavation	Very Stiff	Indented by thumbnail. Slight indentation produced by the blow of the pick point. Requires power tools for excavation.
4. STRUCTURE		5. SOIL TYPE	
Term	Description	Term	Size ( mm )
Intact	Absence of fissures or joints	Boulder	>200
Fissured	Presence of closed joints	Pebbles	60 – 200
Shattered	The presence of closely spaced air-filled joints giving cubical fragments	Gravel	60 – 2
Micro-shattered	Small-scale shattering with shattered fragments the size of sand grains	Sand	2 – 0,06
Slickensided	Polished planar surfaces representing shear movement in soil	Silt	0,06 – 0,002
Bedded Foliated	Many residual soils show structures of parent rock.	Clay	<0,002
6. ORIGIN		5.2 Soil Classification	
6.1 Transported Soils			
Term	Agency of Transportation		
Colluvium	Gravity deposits		
Talus	Scree or coarse colluvium		
Hillwash	Fine colluvium		
Alluvial	River deposits		
Aeolian	Wind deposits		
Littoral	Beach deposits		
Estuarine	Tidal-river deposits		
Lacustrine	Lake deposits		
6.2 Residual soils			
These are products of in situ weathering of rocks and are described as e.g. Residual Shale			
6.3 Pedocretes			
Formed in transported and residual soils etc. calcrete, silcrete, manganocrete and ferricrete.			



## SUMMARY OF DESCRIPTIONS USED IN ROCK CORE LOGGING

1. WEATHERING				
Term	Symbol	Diagnostic Features		
Residual Soil	W5	Rock is discoloured and completely changed to soil in which the original rock fabric is completely destroyed. There is a large change in volume.		
Completely Weathered	W5	Rock is discoloured and changed to soil but the original fabric is mainly preserved. There may be occasional small corestones.		
Highly Weathered	W4	Rock is discoloured, discontinuities may be open and have discoloured surfaces, and the original fabric of the rock near the discontinuities may be altered; alteration penetrates deeply inwards, but corestones are still present.		
Moderately Weathered	W3	Rock is discoloured, discontinuities may be open and will have discoloured surfaces with alteration starting to penetrate inwards, intact rock is noticeably weaker than fresh rock.		
Slightly Weathered	W2	Rock may be slightly discoloured, particularly adjacent to discontinuities, which may be open and will have slightly discoloured surfaces, the intact rock is not noticeably weaker than the fresh rock.		
Unweathered	W1	Parent rock showing no discolouration, loss of strength or any other weathering effects.		
2. HARDNESS			3. COLOUR	
Classification	Field Test	Compressive Strength Range MPa	The predominant colours or colour combination are described including secondary colouration described as banded, streaked, blotched, mottled, speckled or stained.	
Extremely Soft Rock	Easily peeled with a knife	<1		
Very Soft Rock	Can be peeled with a knife. Material crumbles under firm blows with the sharp end of a geological pick.	1 to 3		
Soft Rock	Can be scraped with a knife, indentation of 2 to 4 mm with firm blows of the pick point.	3 to 10		
Medium Hard Rock	Cannot be scraped or peeled with a knife. Hand-held specimen breaks with firm blows of the pick.	10 to 25		
Hard Rock	Point load tests must be carried out in order to distinguish between these classifications	25 - 70		
Very Hard Rock	These results may be verified by uniaxial compressive strength tests on selected samples.	70 - 200		
Extremely Hard Rock		>200		
4. FABRIC				
4.1 Grain Size		4.2 Discontinuity Spacing		
Term	Size (mm)	Description for: Bedding, foliation, laminations	Spacing (mm)	Descriptions for joints, faults, etc.
Very Coarse	>2,0	Very Thickly Bedded	> 2000	Very Widely
Coarse	0,6 – 2,0	Thickly Bedded	600 – 2000	Widely
Medium	0,2 – 0,6	Medium Bedded	200 – 600	Medium
Fine	0,06 – 0,2	Thinly Bedded	60 – 200	Closely
Very Fine	< 0,06	Laminated	3 – 60	Very closely
		Thinly Laminated	<3	
5. ROCK NAME			6. STRATIGRAPHIC HORIZON	
Classified in terms of origin:				
IGNEOUS	Granite, Diorite, Gabbro, Syenite, Dolerite, Trachyte, Andesite, Basalt.			Identification of rock type in terms of stratigraphic horizons.
METAMORPHIC	Slate, Felsite, Gneiss, Schist, Quartzite			
SEDIMENTARY	Shale, Mudstone, Siltstone, Sandstone, Dolomite, Conglomerate, Tillite, Limestone.			

# Appendix B

## Soil Profile Descriptions




DWALA GROUP  
No Limitations

NHBRC  
House Bernard

HOLE No: HB1  
Sheet 1 of 1

JOB NUMBER: 100150



CONTRACTOR :  
MACHINE : PICKS AND SHOVELS  
DRILLED BY :  
PROFILED BY : LM  
TYPE SET BY : LM  
SETUP FILE : STANDARD.SET

INCLINATION :  
DIAM :  
DATE :  
DATE : 21/02/2024  
DATE : 24/03/2024 18:29  
TEXT : ..HouseBernardProfiles.txt

ELEVATION :  
X-COORD :  
Y-COORD :

HOLE No: HB1  
Mossel Bay




NHBRC  
House Bernard

DWALA GROUP  
No Limitations

**HOLE No: HB2**  
**Sheet 1 of 1**

**JOB NUMBER: 100150**



END OF HOLE.

NOTES

- 1) Sidewalls are stable.
- 2) No refusal.
- 3) No groundwater seepage intercepted.

CONTRACTOR :  
MACHINE : PICKS AND SHOVELS  
DRILLED BY :  
PROFILED BY : LM  
TYPE SET BY : LM  
SETUP FILE : STANDARD.SET

INCLINATION :  
DIAM :  
DATE :  
DATE : 21/02/2024  
DATE : 24/03/2024 18:29  
TEXT : ..HouseBernardProfiles.txt

ELEVATION :  
X-COORD :  
Y-COORD :

**HOLE No: HB2**  
**Mossel Bay**










DWALA GROUP  
No Limitations

NHBRC  
House Bernard

**LEGEND**  
Sheet 1 of 1

JOB NUMBER: 100150

	SAND	{SA04}
	SANDY	{SA05}
	CLAY	{SA08}
	CLAYEY	{SA09}
	BRICKWALL	{SA14}
	CONCRETE	{SA34}
	DISTURBED SAMPLE	{SA38}

Name ●

CONTRACTOR :  
MACHINE :  
DRILLED BY :  
PROFILED BY :

TYPE SET BY : LM  
SETUP FILE : STANDARD.SET

INCLINATION :  
DIAM :  
DATE :  
DATE :

DATE : 24/03/2024 18:29  
TEXT : ..HouseBernardProfiles.txt

ELEVATION :  
X-COORD :  
Y-COORD :

**LEGEND**  
SUMMARY OF SYMBOLS

# Appendix C

## Laboratory Test Results



# OUTENIQUA LAB (Pty) Ltd.

Registration No. 95/07742/07

Materials Testing Laboratory

6 Mirrorball Street, George : PO Box 3186, George Industria, 6536

Tel: 044 8743274 : Fax: 044 8745779 : e-mail: llewelyn@outeniqualab.co.za

R-FIND-1-6

Jan-22




T0347

Customer :	Dwala Group (Pty) Ltd Postnet Suite 073 Private Bag X1, Menlo Park 102	Project :	House Bernard - Mossel Bay
	Attention :		Nhlanhla Magigaba
		Date Reported :	20/03/2024
		Req. Number :	0492/24
		No. of Pages :	1

## TEST REPORT FOUNDATION INDICATOR - (ASTM Method D422)

Sample Position (SV)	HB1	
Depth (mm):	800-1100	
Sample No.:	87837	
Materials Description	Source	In-situ
	Colour	Light Grey
	Soil Type	Silty Sand
	Classification	Existing



75.0mm	100
63.0mm	100
53.0mm	100
37.5mm	100
26.5mm	100
19mm	100
13.2mm	100
9.5mm	100
6.7mm	99
4.75mm	99
2.36mm	88
1.18mm	78
0.6mm	70
0.425mm	65
0.075mm	44
0.064mm	42
0.047mm	36
0.022mm	30
0.006mm	28
0.005mm	24
0.003mm	24
0.002mm	24
0.001mm	24



Liquid Limit (%)	45
Plasticity Index (%)	12
Linear Shrinkage (%)	6
Moisture Content (%)	32.9

% Clay	24
% Silt	17
% Sand	44
% Gravel	15

Unified Soil Classification	SM
AASHTO Soil Classification	A-7-5



• Specimen delivered to Outeniqua Lab in good order.

Ruan Lesch  
Technical Signatory  
For Outeniqua Lab (Pty) Ltd.

Copyright © 2014 Llewelyn Heathcote. All Rights Reserved.

- This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Directors of Outeniqua Lab.
- Measuring Equipment, traceable to National Standards is used where applicable. Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and / or taken.
- While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.

# Appendix D


## Settlement Calculations




## PREDICTION OF THE AVERAGE ELASTIC SETTLEMENT OF A STRIP FOOTING

PROJECT NAME	House Bernard
PROJECT NUMBER	100150
PROBLEM DESCRIPTION	HB1 - Settlement on current in-situ residual material
LOCATION	Mossel Bay

FOUNDING DEPTH ( D )	0,8 m
WIDTH OF THE FOOTING ( B )	0,96 m
THICKNESS OF COMPRESSIBLE STRATUM ( H )	2 m
STIFFNESS OF COMPRESSIBLE STRATUM	7 MPa
FOUNDATION PRESSURE ( q )	150 kPa
H / B	2,08
D / B	0,83
U <sub>1</sub> - INFLUENCE FACTOR	0,89
U <sub>0</sub> - INFLUENCE FACTOR	0,91
<b>AVERAGE IMMEDIATE SETTLEMENT ***</b>	17 mm



\*\*\* - After Janbu, Bjerrum and Kjaernsli for  $L/D < 10$  only



# Appendix E

## Site plan

