



**STRUCTURAL ASSESSMENT AT HOUSE VAN DYK, 58 PRIDE OF INDIA
CRESENT IN WAVECREST OF JEFFREYS BAY**

**DETAILED FORENSIC REPORT:
STRUCTURAL ENGINEERING REV 2**

MAY 2024

PREPARED FOR:



THE PROJECT MANAGER

NHBRC

40 PICKERING STREET

NEWTON PARK

GQEBERHA (PORT ELIZABETH)

Tel (041) 365 0301 Fax (041) 365 4101

PREPARED BY:



GAUTENG PROVINCE OFFICE

27 MULLER STREET NORTH, BUCCLEUCH

SANDTON, JOHANNESBURG,

2090

Tel: (011) 802 0286

Fax: (086) 606 3734

EASTERN CAPE PROVINCE OFFICE

87 WESTVIEW DRIVE, MILL PARK,

GQEBERHA (PORT ELIZABETH)

Tel: (041) 363 0189

Email: corporate@shumbaengineering.co.za

Contact Person: A Mloyiswa

CONTENTS

Chapter	Description	Page
	Abbreviations / Acronyms / Definitions	3
	List of Figures	3
	Document Information and Approvals	4
	Executive Summary	5
1	Introduction	6
2	Purpose of the Report	6
3	Project Location	7
4	Assessment Methodology and Approach	8
	4.1 Structural Engineering Assessment Methodology	8
5	Structural Engineering Assessment Findings	9
	5.1 Geotechnical and Topographical Condition	9
	5.2 External Brick Walls Condition	9
	5.3 Internal Brick Walls Condition	10
	5.4 Roof and Roof Trusses Condition	10
	5.5 Surface Bed Floor Condition	10
	5.6 Foundation Condition	10
6	Remedial Scope	11
	6.1 External Brick Walls	11
	6.2 Internal Brick Walls	12
	6.3 Roof and Roof Trusses	12
	6.4 Surface Beds and Floor Condition	13
	6.5 Foundations	13
7.	Summary of Findings and Remedial Action	14
8	Recommendations	15
	Document Control and Disclaimer	16

9	Appendices	17
	Appendix A: Drawing for Foundation Underpinning	17
	Appendix B: Typical Drawing: Beam at Window/Door Level, Apron and V-Drain Details	18
	Appendix C: Structural Engineering Photographic Report	19
	Appendix D: Geotechnical Field Report	25

Abbreviations / Acronyms / Definitions

NHBRC	National Home Builders Registration Council
DPC	Damp Proof Course
SES	Shumba Engineering Services
RC	Reinforced Concrete
SANS	South African National Standards

List of Figures

Figure 1 : House Van Dyk District Locality Plan adopted from Google Earth on 15 March 2023	7
Figure 2 : House Van Dyk Locality Plan adopted from Google Earth on 15 March 2023	7

Document Information and Approvals

TITLE		STRUCTURAL ASSESSMENT AT HOUSE VAN DYK, 58 PRIDE OF INDIA CRESENT IN WAVECREST OF JEFFREYS BAY
Client		NHBRC
CONTRACT No.		ETS-CM-010836-WN
Key Words		Structural engineering services, structural engineering assessment findings, conclusions and recommendations, scope of work, Geotechnical investigations
Date of this issue		21 May 2024

For: SHUMBA ENGINEERING SERVICES (SES)

Compiled by:

C W Molokomme

Initial & Surname



Signature

21 May 2024

Date

Reviewed by:

G. Kucherera (Pr. Eng.)

Initial & Surname

Signature

21 May 2024

Date

Approved by:

A. Mloyiswa (Pr. Eng, Pr CPM, MSAICE)

Initial & Surname

Signature

21 May 2024

Date

NHBRC

Received by:

Initial & Surname

Signature

Date

Approved by:

Initial & Surname

Signature

Date

Executive Summary

In order to restore house Van Dyk to be a functional facility that meets acceptable norms and standards, the National Home Builders Registration Council (NHBRC) appointed Shumba Engineering Services (SES) as professional Structural Engineers to conduct a condition assessment of the building amongst other services. The scope of the condition assessment included identifying defective structural elements, performing structural infrastructure capacity checks, proposing repair methods and recommendations proposals.

As part of their assessment, Shumba Engineering Services performed a visual assessment of various elements of the building facility, took photographs, performed structural infrastructure design capacity checks and drew conclusions and recommendations from the information obtained. Remedial proposals and upgrading solutions were tabled for structural engineering defects that were observed. A photographic record of the condition of the various elements of the building was compiled and presented as part of the findings in the report. Finally a general and summarised proposed structural engineering scope of work was tabled.

The site appears to have averagely poor founding material. There is a gentle slope towards the northern side of the site. The general structural integrity condition of the existing external walls appears to be fairly good. However, there are cracks on the external wall which range from about 0.5mm wide (minor) to about 4mm wide (major). There is a major diagonal crack on the main bedroom external brick wall showing signs of significant foundation settlement. The homeowner, Mr Van Dyk, confirmed that there were severe municipal water pipe leakages within the premises before. Additionally, it appears the water leakages might have contributed to this major foundation settlement as this is the lowest point in the direction of water flow.

There are no aprons or stormwater channels around the building. There is a major diagonal to vertical crack on the main bedroom internal wall (about 4mm wide) showing signs of major foundation settlement. There is dampness on the main bedroom internal brick wall. It appears the dampness on these walls are due to the bathroom showers. The structural condition of all surface beds floor appears good with very minor hair line cracks on the floor tiles. The structural condition of the roof trusses appears very good showing no signs of structural defects. There are no roof gutters and there are no rainwater downpipes on the entire building. The external foundation wall of the main bedroom shows lateral movement below the DPC level.

It is recommended that new aprons or stormwater channels are constructed. The horizontal crack around the entire external wall at floor level must be repaired by removing the mortar bed within the crack, cut to trim back the DPC and apply a new mortar bed or SANS approved polyurethane sealants. All vertical and diagonal cracks on internal brick walls less than 2.5mm cracks are to be repaired by removing plaster for a width of 300mm on either side of the crack, clean with compressed air to remove dust and loose material, nail fixing a 600mm wide galvanised wire mesh spanning over the crack and replaster over. All major cracks, however, must be repaired as per typical detail in figure 3. Roof gutters and rainwater downpipes should be installed to divert storm water away from the building's foundations. Additionally, new concrete aprons and or stormwater channels must be installed. The isolation joint sealant between surface bed and brick wall must be carefully removed and reinstalled using Sikaflex PRO-3 i-cure polyurethane sealants or similar SANS approved products.

1 Introduction

Shumba Engineering Services was appointed by the National Home Builders Registration Council (NHBC) as their preferred Structural Consulting Engineering service provider for the House Van Dyk in Jeffreys Bay (Kouga Municipality) in the Sarah Baartman District Municipality of Eastern Cape Province of South Africa. The scope of services expected from Shumba Engineering Services primarily includes the following:

- Structural Condition Assessment and;
- Reporting.

The project scope is expected to include the following summarised activities:-

1. Renovations/remedials to existing building which includes;
 - Remedial works to external brick walls, internal brick walls and surface beds;
 - Foundation underpinning;
 - New roof gutters and rainwater downpipes;
 - New aprons and stormwater channels around existing building.

In order to restore the existing building and upgrade the house structural infrastructure, a structural engineering condition assessment was conducted to determine the condition of the house. Various defects were observed and recorded. Remedial proposals to correct the defects were tabled.

2 Purpose of the Report

The purpose of this document is to report on the following:

- The condition of the existing building and structural engineering elements.
- The defective building's structural engineering elements and the scope of work and remedial procedure to follow.

3 Project Location

House Van Dyk is in Jeffreys Bay (Kouga Municipality) in the Sarah Baartman District Municipality of Eastern Cape Province of South Africa. The reference coordinates of the site are 34°00'50.55"S and 24°54'50.71"E. A map of the general location within the Sarah Baartman District Municipality as well as a locality map of House Van Dyk is shown in Figures 1 and 2 respectively.




Figure 1 : House Van Dyk District Locality Plan adopted from Google Earth on 15 March 2023




Figure 2 : House Van Dyk Locality Plan adopted from Google Earth on 15 March 2023

4 *Assessment Methodology and Approach*

4.1 **Structural Engineering Assessment Methodology**

Structural engineering assessment was conducted on the 28th February 2023 in accordance with the following methodology:

An initial visual **site inspection and assessment** was conducted to identify of all defective elements. All the information was compiled into this condition assessment report. During the assessment, **consultation** with the current house owner was performed to understand any further structural related problems that they face.

A **desk top study** of the project location, available project information and documentation of photographs taken during the site inspection was undertaken and conclusions drawn from this information. There were no structural drawings, topographical survey and architectural drawings provided at the time of structural assessment. However, a geotechnical field investigation report undertaken by Dwala group was provided to SES by the NHBRC to further understand the foundation conditions.

Documentation of the photographic report and main report framework was performed. Specific remedial measures, specifications and proposed scope of work were drawn and passed onto the project consulting team members. All the above were compiled into this condition assessment report. The report should be used as a basis for making decisions regarding the remedial works of various defected structural elements of the building.

5 *Structural Engineering Assessment Findings*

5.1 Geotechnical and Topographical Condition

The following observations were made regarding the geotechnical conditions across the site:

- The entire site appears to have poor founding material;
- There is a gentle slope towards the north direction across the entire site. However, no topographical survey was available at the time of the site assessment.

A copy of the Geotechnical field investigation report is shown in Appendix D of this report.

5.2 External Brick Walls Condition

The following observations were made regarding the existing external wall of the building:

- The existing structure was constructed out of brick walls;
- All existing external walls are brick cavity wall consisting of face-brick on the outside face and plastered brick on the inside face of the building;
- The general structural integrity condition of the existing external walls appears to be fairly good. However, there are several cracks on the external wall which ranges from about 0.5mm wide (minor) to about 4mm wide (major) showing signs of foundation settlement;
- There is a horizontal crack around the entire external wall at floor level (DPC level). It appears the horizontal crack is due to a bond mortar separation in-between the DPC and mortar bed course;
- There are diagonal cracks on the external brick wall above windows showing signs of foundation settlement. The crack width range from about 0.1mm to about 2mm;
- There is a major horizontal crack on the external brick wall above the back entrance door. The crack is about 4mm wide. It appears the crack is due to insufficient supporting capacity for the timber roof trusses;
- There is a major diagonal crack on the main bedroom external brick wall showing signs of foundation settlement;
- There are no aprons or stormwater channels around the building;
- The homeowner, Mr Van Dyk, confirmed verbally that there were severe municipal water pipe leakage within the premises which totalled to about 180kl in one month. Additionally, it appears the water leakage might have contributed to this foundation settlement. All municipal water pipes runs above ground and all underground pipes have now been disconnected ;

A photographic record of the building's external wall is shown in Appendix C of this report.

5.3 Internal Brick Walls Condition

The following observations were made regarding the internal brick walls:

- There are several diagonal cracks (about 0.5mm wide to 3mm wide) above the windows showing signs of settlement;
- There is a horizontal crack (about 2mm to 4mm wide) on the internal wall above lintel level of the sitting room window and above back entrance door;
- There is a diagonal-vertical crack on the internal brick wall next to the lounge/garage entrance;
- There is a major diagonal to vertical crack on the main bedroom internal wall (about 4mm wide) showing signs of foundation settlement;
- There is dampness on the main bedroom internal brick wall. It appears the dampness on these internal bedroom walls are due to the bathroom showers;

A photographic record of the building's internal wall is shown in Appendix C of this report.

5.4 Roof and Roof Trusses Condition

The following observations were made regarding the roof trusses:

- The structural condition of the roof trusses appears very good showing no signs of structural defects;
- There are no roof gutters and there are no rainwater downpipes on the entire building.

A photographic record of the building's roof trusses is shown in Appendix C of this report.

5.5 Surface Bed Floor Condition

The following observations were made regarding the surface bed floors:

- All surface bed floors are tiled with ceramic floor tiles;
- The structural integrity condition of all surface beds floor appears good with very minor hair line cracks on the floor tiles;
- The veranda's isolation joint sealant between surface beds and brick walls is delaminating. It appears there is a slight settlement of either the surface bed or brick wall;
- The edge floor tiles on the veranda have been replaced. It appears floor tiles were installed with half the portion over brick and half portion on surface bed. Due to the building settlement this has caused the floor tiles to crack and delaminate in certain places.

A photographic record of the building's surface bed floor is shown in Appendix C of this report.

5.6 Foundation Condition

The following observations were made regarding the foundation:

- The building appears to be supported on strip footings;
- No structural drawings are available at this stage and it is unclear whether the foundations are reinforced or not.
- There is lateral movement of the foundation wall of the main bedroom below the DPC level which could be due to the reaction of the weaker underlying soil conditions.

A copy of the Geotechnical field report is shown in Appendix D of this report.

6 Remedial Scope

6.1 External Brick Walls

All existing external walls are brick cavity wall consisting of face-brick on the outside face and plastered brick on the inside face of the building. There is a horizontal crack around the entire external wall at floor level (DPC level). It appears the horizontal crack is due to a bond mortar separation in-between the DPC and mortar course bed. There are diagonal cracks on the external brick wall above windows showing signs of foundation settlement. The crack's width ranges from about 0.1mm to about 2mm. There is a major horizontal crack on the external brick wall above the back entrance door. The crack is about 4mm wide. It appears the crack is due to insufficient supporting capacity for the timber roof trusses. There is a major diagonal crack on the main bedroom external brick wall showing signs of a significant foundation settlement. There are no aprons or stormwater channels around the building.

It is recommended that:

- The horizontal crack around the entire external wall at floor level must be repaired by removing the mortar bed within the crack, cut to trim back the DPC and apply a new mortar bed or SANS approved polyurethane sealants;
- Minor vertical and diagonal cracks (less than 2mm wide) on external brick walls must be repaired by removing mortar bed within the cracks and applying new mortar bed. However, for major vertical and diagonal cracks (about +3mm wide), it is recommended that these cracks are repaired as per detail in figure 3 below;
- A major horizontal crack on the external brick wall above the back entrance door must be repaired by carefully removing the lintel above the door/window, replace the lintel with a new RC beam and grout in between the lintel and existing brick above. Alternatively, demolish the lintel and brick wall above lintel and reconstruct with new RC beam and new brick wall. The construction sequence of this repair must be closely coordinated by the engineer as it will involve high risk occupational health and safety during propping of the roof trusses and demolish;
- The major diagonal cracks on the brick wall above the main bedroom window must be repaired by carefully removing the existing brickwork above the window and replace with the new RC lintels;
- New aprons or v-channels must be constructed all the entire building to divert storm water way from the building.




Figure 3: Typical crack repair

6.2 Internal Brick Walls

There are several diagonal cracks (about 0.5mm wide to 3mm wide) above the windows showing signs settlements. There is a horizontal crack (about 2mm to 4mm wide) on the internal wall above lintel level of the sitting room window and above back entrance door. There is a diagonal-vertical crack on the internal brick wall next to lounge/garage entrance. There is a major diagonal to vertical crack on the main bedroom internal wall (about 4mm wide) showing signs of major foundation settlement. There is dampness on the main bedroom internal brick wall. It appears the dampness on these internal bedroom walls are due to the bathroom showers.

It is recommended that:

- All vertical and diagonal cracks on brick walls less than 2.5mm cracks are to be repaired by removing plaster for a width of 300mm on either side of the crack, clean with compressed air to remove dust and loose material, nail fixing a 600mm wide galvanised wire mesh spanning over the crack and replaster over. All major cracks however, must be repaired as per typical detail in figure 3 above;
- The horizontal crack (about 2mm to 4mm wide) on the internal wall above lintel level of the sitting room window and above back entrance door must be repaired by carefully removing the lintel above the door/window, replace the lintel with a new RC beam and grout in between the lintel and existing brick above. Alternatively, demolish the lintel and brick wall above lintel and reconstruct with new RC beam and new brick wall. The construction sequence of this repair must be closely coordinated by the engineer as it will involve high risk occupational health and safety during propping of the roof trusses and demolish;
- The dampness on the wall must be repaired by removing the plaster and applying SANS approved waterproofing products.

6.3 Roof and Roof Trusses

The structural condition of the roof trusses appears very good showing no signs of structural defects. There are no roof gutters and there are no rainwater downpipes on the entire building. It is recommended that:

- Roof gutters and rainwater downpipes must be installed to divert stormwater away from the building's foundations. Additionally, new concrete aprons and or stormwater channels must be installed.

6.4 Surface Beds and Floor Condition

All surface bed floors are tiled with ceramic floor tiles. The structural integrity condition of all surface bed floor appears good with very minor hairline cracks on the floor tiles. The isolation joint sealant between the surface bed and the brick wall is delaminating showing signs of slight movement of the surface bed and or brick wall. The edge floor tiles on the two outside verandas have been replaced. It appears floor tiles were installed with half the portion over brick and half portion on the surface bed. Due to the building settlement this has caused the floor tiles to crack and delaminate.

It is recommended that:

- The isolation joint sealant between the surface bed and brick wall must be carefully removed and reinstalled using Sikaflex PRO-3 i-cure polyurethane sealants or similar SANS-approved products;
- All veranda edge floor tiles installed with half the portion over brick and half the portion on the surface bed must be removed and reinstalled with an isolation joint between the surface bed and brick wall. This will prevent the tiles from further cracking.

6.5 Foundations

The building appears to be supported on strip footings. However, no structural drawings are available at this stage and it is unclear whether the foundations are reinforced or not. The north side of the building appears to have severe cracks showing signs of settlement.

It is recommended that:

- All external brick wall foundation on the north side of the building be underpinned with RC concrete. The underpinning must be designed and supervised by a competent Structural Engineer. All cracks on the north side of the building should be repaired after underpinning construction is done;

Specification for Underpinning Works

- Foundation underpinning shall be done on the entire external wall of the northern and western sides of the building.
- The Contractor shall submit a proposed sequence of underpinning blocks for approval by the Engineer before excavations. For example, the sequence shall be such that all sections marked 1 will be excavated, cast and dry-packed before starting excavation of sections marked 2; and all sections marked 2 will be excavated, cast and dry-packed before starting excavation of sections marked 3, etc.
- The contractor is to keep a record of the sequence and dimensions of the underpinning actually carried out, including details of excavation, casting concrete and pinning up for each section.
- Before starting the work the Contractor is to check for any services that could be damaged by the underpinning work.
- The Contractor shall be responsible for ensuring that his operations do not in any way impair the safety or condition of the building both before and during the execution of the work and should immediately inform the Engineer if he considers that more stringent procedures than those specified are necessary.
- Excavation and concreting of any section of underpinning shall be carried out on the same day.

- The underside of the existing footings is to be cleaned of all loose materials or soil before underpinning.
- Excavation to any section of underpinning shall not be started until at least 48 hours after completion of any section/s of the work.
- The disturbed soil beneath existing footings shall be well compacted before constructing any concrete works related to underpinning.

Projecting portions of existing footings are to be carefully cut off where directed.

Place a 50mm concrete blinding layer (10MPa) on the compacted soil layer before underpinning.

The bottom of the underpinning to be reinforced with Ref. 617 mesh placed 50mm above the blinding layer.

Underpinning is to be carried out in small sections of 1.5m length x 0.8m width x 0.8m depth. The new underpinning foundation blocks shall be spaced 1.0m apart.

The body of the underpinning is to be constructed in 25MPa/19mm reinforced concrete and in to be cast to the widths shown unless otherwise directed by the Engineer.

- The mass concrete is to be stopped off 50mm below the underside of the existing footing.
- The final pinning up over the whole width of the footing is to be carried out with 1:3 mix cement to sharp sand (wholly free from foreign particles) dry pack mortar 24 hours after the concrete has been poured.
- Excavated material intended for backfilling is to be kept protected from drying out or wetting and is to be placed in a maximum of 150mm layers, carefully compacted with a compacting plate.
- And unless a proper dewatering method is used, the works should not be attempted on wet ground.

7. Summary of Findings and Remedial Action

Item no.	Area Description	Findings	Remedial Measure
1	Roof	No roof gutters and rainwater downpipes	Installation of roof gutters and rainwater downpipes. Additionally, aprons and stormwater channels to divert stormwater.
2	Main bedroom	Minor diagonal and vertical cracks	Nail-fixing galvanized wire mesh and plastering over
		Major diagonal cracks on the internal and external brick walls	Wall stitching, as per typical detail in Figure 3 Install a new concrete lintel above the window level.
		Dampness on the internal brick wall	Removing the plaster and applying SANS approved waterproofing product
3	Sitting room	Horizontal crack (on the internal wall above lintel level)	Replace the existing wall with a new 25MPa/19 reinforced concrete beam above the window level
4	Lounge/garage	Minor diagonal to vertical	Nail-fixing galvanized wire mesh and

	entrance	crack on the internal brick wall	plastering over minor cracks (refer to a method in paragraph 6.2)
		Major diagonal to vertical crack on the interior wall	To be repaired through wall stitching, as per typical detail in Figure 3
5	Outside Verandas x 2	Floor tiles installed with half the portion over brick and half portion on surface bed causing them to crack	Removed and reinstall tiles with an isolation joint between the surface bed and brick wall
6	Back Entrance	Diagonal cracks on the external brick wall above the door/window	Replace the existing lintel with a new 25MPa/19 reinforced concrete beam above the door/window level
7	Surface Beds	Very minor hairline cracks on the floor tiles	Replace damaged tiles with similar or equivalent type
		Isolation joint sealant between the surface bed and the brick wall is delaminated	Reinstate seal using Sikaflex PRO-3 i-cure polyurethane sealants or similar SANS-approved products
		Horizontal crack around the entire external wall at the DPC level	Apply a new mortar bed or SANS-approved polyurethane sealants (see paragraph 6.4)
8	Foundations	Differential settlement	Concrete underpinning as per specifications in paragraph 6.5 and drawing in Appendix A
		Lateral movement of foundation wall near the main bedroom	Concrete Underpinning as per specifications in paragraph 6.5 and drawing in Appendix A
9	Stormwater Drainage	No gutters and drain pipes around the entire house	New 25MPa concrete aprons and stormwater channels around the existing building

8 Recommendations

The following structural engineering scope of work is therefore proposed:

- Remedial works to external brick walls, internal brick walls and surface beds;
- Foundation underpinning;
- The homeowner should consider installing new roof gutters and rainwater downpipes;
- New aprons and stormwater channels around the existing building;


Document Control and Disclaimer

CLIENT : National Home Builders Registration Council (NHBC)

PROJECT NAME : STRUCTURAL ASSESSMENT AT HOUSE VAN
DYK, 58 PRIDE OF INDIA CRESENT IN
WAVECREST OF JEFFREYS BAY.

PROJECT No. :

TITLE OF DOCUMENT : Structural Engineering Assessment Report Rev 2– May 2024

	Prepared By	Reviewed By	Approved By
ORIGINAL	NAME CW MOLOKOMME	NAME GRANT KUCHERERA	NAME ALEXANDER MLOYISWA
DATE May 2024	SIGNATURE 	SIGNATURE	SIGNATURE

This report, and information or advice, which it contains, is provided by Shumba Engineering Services (SES) (or any of its related entities) solely for internal use and reliance by its Client in performance of SES's duties and liabilities under its contract with the Client. Any advice, opinions, or recommendations within this report should be read and relied upon only in the context of the report as a whole. The advice and opinions in this report are based upon the information made available to SES at the date of this report and on current South African standards, codes, technology and construction practices as at the date of this report. Following final delivery of this report to the Client, SES will have no further obligations or duty to advise the Client on any matters, including development affecting the information or advice provided in this report. This report has been prepared by SES in their professional capacity as Consulting Engineers. The contents of the report do not, in any way, purport to include any manner of legal advice or opinion. This report is prepared in accordance with the terms and conditions of the SES contract with the Client. Regard should be had to those terms and conditions when considering and/or placing any reliance on this report. Should the Client wish to release this report to a Third Party for that party's reliance, SES may, at its discretion, agree to such release provided that:

- SES's written agreement is obtained prior to such release, and
- By release of the report to the Third Party, that Third Party does not acquire any rights, contractual or otherwise, whatsoever against SES and SES, accordingly, assume no duties, liabilities or obligations to that Third Party, and
- SES accepts no responsibility for any loss or damage incurred by the Client or for any conflict of SES interests arising out of the Client's release of this report to the Third Party.



GAUTENG PROVINCE OFFICE
27 MULLER STREET NORTH, BUCCLEUCH
SANDTON, JOHANNESBURG,
2090

Tel: (011) 802 0286
Fax: (086) 606 3734


EASTERN CAPE PROVINCE OFFICE

87 WESTVIEW DRIVE, MILL PARK,
GQEBERHA (PORT ELIZABETH)
Tel: (041) 363 0189

Email: corporate@shumbaengineering.co.za
Contact Person: A Mloyiswa

9 *Appendices*

Appendix A: Drawing for Foundation Underpinning





SECTION FOUNDATION UNDERPINNING (1.5m x 0.8m x 0.8m)

SCALE: N . T . S

**Appendix B: Typical Drawing: Beam at Window/Door Level,
Apron and V-Drain Details**


THESE NOTES SHALL BE PART OF THE SPECIFICATION IN THOSE CASES WHERE THESE NOTES DIFFER FROM APPROPRIATE CONSTRUCTION DETAILS. THE CONTRACTOR SHALL BE RESPONSIBLE TO THE STRUCTURAL ENGINEER WHO SHALL MAKE THE FINAL DECISION.

- CONCRETE NOTES:**
- 1.1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE RELEVANT AUTHORITIES BEFORE COMMENCING WORK.
 - 1.2. ALL DIMENSIONS AND HEIGHTS ARE TO BE CHECKED IN THE FIELD BEFORE COMMENCING WORK.
 - 1.3. REPORT DISCREPANCIES TO ARCHITECT OR ENGINEER.
 - 1.4. THIS DRAWING IS NOT TO BE USED TO SCALE OFF. USE ONLY WRITTEN DIMENSIONS. CONTACT THE ENGINEER OR ARCHITECT IN CASE OF A DISCREPANCY.
 - 1.5. FOR SETTING OUT DATA, SETTING OUT POINTS AND DATUM LEVELS REFER TO ARCHITECTURAL AND CIVIL ENGINEERING DRAWINGS WHERE THERE IS A DISCREPANCY OF LEVELS BETWEEN THE ARCHITECTURAL AND STRUCTURAL DRAWINGS, THE ARCHITECTURAL DRAWINGS SHALL TAKE PRECEDENCE.
 - 1.6. PROJECT SPECIFICATION AND RELEVANT S.A.S SPECIFICATIONS WITH THE PROJECT SPECIFICATION SHALL BE COMPLIED WITH IN ACCORDANCE WITH THE PROJECT SPECIFICATION.
 - 1.7. ALL CONCRETE WORKS TO BE DONE IN ACCORDANCE WITH S.A.S 1000 AND RELEVANT ARCHITECTURAL, MECHANICAL, ELECTRICAL & PLUMBING DRAWINGS AND DETAILS AS SHOWN FOR WORK.
 - 1.8. STORMWATER OUTLETS, SHOPS AND HOLES AND SLEEVES FOR THESE SERVICES SHALL BE TO BE COVERED BEFORE FINISHING WITHIN APPROVAL.
 - 2.0. CONCRETE
 - 2.1. ALL CONCRETE EXCAVATIONS TO BE INSPECTED AND APPROVED IN WRITING BY THE ENGINEER BEFORE CONCRETE IS CAST.
 - 2.2. NO EXCAVATIONS ARE TO BE CAST UNTIL MINIMUM 1.50m THICK LAYERS OF 100mm 19mm BLENDED CONCRETE IS TO BE CAST UNDER ALL REINFORCED BRICKS, REINFORCED STEEL FOOTINGS AND GROUND BEAMS.
 - 2.3. ANY OTHER EXCAVATIONS ARE TO BE MADE GOOD WITH 100mm 19mm CONCRETE AT THE CONCRETE EXPOSED.
 - 2.4. BACKFILLING OVER COLUMN BASES SHALL BE DONE WITH AN APPROVED MATERIAL COMPACTED IN LAYERS IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 2.5. CONCRETE TESTS
 - 2.6. CONCRETE TESTS SHALL BE DONE UNDER THE FOLLOWING SPECIFICATIONS:
 - 2.6.1. ALL CONCRETE BEING CAST UNDER PRESSURE UNDER 20MPa
 - 2.6.2. STRIP FOOTINGS 20MPa
 - 2.6.3. RETAINING WALL STRIP FOOTINGS 20MPa
 - 2.6.4. CONCRETE 25MPa
 - 2.7. CONCRETE CHARACTERISTIC 28 DAY STRENGTH:
 - 2.7.1. SUPPLEMENTED SLAB & BEAM 20MPa 19mm
 - 2.7.2. CONCRETE TEST CUBE TEST RESULTS TO BE SUBMITTED TIMELY TO THE ENGINEER FOR APPROVAL.
 - 2.7.3. ALL CONCRETE TO BE ADEQUATELY COVERED BY KEEN SURFACES CONTINUOUSLY COVER FOR AT LEAST 14 DAYS FOR CURING.
 - 2.7.4. ALL CONCRETE TO BE CONSTRUCTED TO THE S.A.S 1000.
 - 2.7.5. RESPONSIBLE ENGINEER SIGNATURE OF ACCURATE DATA LESS THAN 14 DAYS.
 - 2.8. CONCRETE CURING:
 - 2.8.1. CONCRETE CURING TEST RESULTS TO BE SUBMITTED TIMELY TO THE ENGINEER FOR APPROVAL.
 - 2.8.2. CONCRETE CURING TO BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.0. REINFORCEMENT
 - 3.1. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS, RELEVANT ARCHITECTURAL, MECHANICAL, ELECTRICAL & PLUMBING DRAWINGS AND DETAILS AS SHOWN FOR WORK.
 - 3.2. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.3. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.4. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.5. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.6. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.7. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.8. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.9. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.10. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.11. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.12. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.13. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.14. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.15. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.16. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.17. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.18. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.19. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.20. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.21. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.22. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.23. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.24. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.25. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.26. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.27. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.28. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.29. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.30. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.31. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.32. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.33. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.34. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.35. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.36. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.37. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.38. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.39. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.40. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.41. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.42. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.43. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.44. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.45. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.46. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.47. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.48. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.49. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.50. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.51. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.52. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.53. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.54. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.55. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.56. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.57. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.58. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.59. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.60. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.61. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.62. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.63. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.64. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.65. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.66. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.67. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.68. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.69. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.70. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.71. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.72. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.73. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.74. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.75. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.76. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.77. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.78. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.79. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.80. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.81. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.82. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.83. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.84. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.85. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.86. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.87. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.88. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.89. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.90. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.91. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.92. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.93. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.94. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.95. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.96. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.97. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.98. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.99. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 - 3.100. REINFORCEMENT SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.



TYPICAL DRAWING: BEAM ELEVATION
320mm x 230mm BEAM (25MPa/19mm)

SECTION A-A: RC BEAM



TYPICAL SECTION OF V-DRAIN AND APRON
25MPa/19mm)

MEMBER	NO OF	DIA	CUT LENGTH	BAR MARK	SC	A	B	C	D	E/R	kg
1	1	R8	1050	01	60	280	180				
	1	Y16	VARIES	02	35	VARIES					

NB: LENGTH OF BARS "VARIES" DEPENDING ON THE WIDTH OF THE DOOR/WINDOW OPENING

- REINFORCEMENT NOTES:**
1. REFER TO DRAWING CONCRETE LAYOUT.
 2. REINFORCEMENT YIELD STRENGTH:
 - Y16: 460MPa
 - R8: 460MPa
 - MILD STEEL: 250MPa
 - WELDED STEEL WIRE MESH: 460MPa
 3. ALL REINFORCEMENT TO CONFORM TO THE REQUIREMENT OF SANS 10162 AND SANS 10163.
 4. ALL REINFORCEMENT CUTTING AND BENDING TO BE DONE IN ACCORDANCE WITH SANS 10162.
 5. ADMITTANCE:
 - B: BOTTOM
 - B1: LOWEST OF THE BOTTOM LAYERS
 - B2: SECOND LOWEST OF THE BOTTOM LAYERS
 - T: TOP
 - T1: HIGHEST OF THE TOP LAYERS
 - T2: SECOND HIGHEST OF THE TOP LAYERS
 - NP: NEAR FACE
 - FP: FAR FACE
 - EF: EACH FACE
 - EW: EACH WAY
 - AS: ALTERNATELY STAGGERED
 - AP: ALTERNATELY PLACED
 - AB: ALTERNATE BAR REVERSED
 - OB: OTHER
 - VER: VERTICAL
 - HOR: HORIZONTAL

No	Date	Issued For	AM
		Details	Chd P000



Service: **STRUCTURAL**
REMEDIAL WORKS FOR HOUSE VAN DYK

Project: **TYPICAL DRAWING: BEAM, APRON AND V-DRAIN DETAILS**

Drawn By: T. Sathupane
Designed By: T. Sathupane
Checked By: H.C. Mookanna

Site: A1
Scale: AS SHOWN
Original Date: FEB 2024

Appendix C: Structural Engineering Photographic Report

Project:
ETS-CM-010836-WN:
Professional Consultancy Services
for House Van Dyk in Jeffreys
Bay in the Sarah Baartman
District
 – STRUCTURAL ENGINEERING
 DISCIPLINE

Report Title:
 Structural Engineering
 condition Assessment Report

Report Sub-Title:
HOUSE VAN DYK
 PHOTOGRAPHIC REPORT

Revision: **02**

Date: **21.05.2024**



Page:
Page 16



Photo 1: Horizontal crack at surface bed level



Photo 2: Bond mortar separation in-between the DPC and mortar course bed .




Photo 3: Horizontal crack at surface bed level



Photo 4: Horizontal crack at surface bed level .



Photo 5: Horizontal crack above back entrance door.



Photo 6: Crack on window seal




Photo 7: No aprons or stormwater around the building.



Photo 8: No aprons or stormwater around the building.



Photo 9: No roof gutters or rainwater downpipe.

Project:
ETS-CM-010836-WN:
Professional Consultancy Services
for House Van Dyk in Jeffreys
Bay in the Sarah Baartman
District
 – STRUCTURAL ENGINEERING
 DISCIPLINE

Report Title:
 Structural Engineering
 condition Assessment Report
 Rev 2

Report Sub-Title:
HOUSE VAN DYK
 PHOTOGRAPHIC REPORT

Revision: **02**

Date: **21.05.2024**



Page:
Page 17



Photo 10: Major vertical-diagonal crack on the internal bedroom wall.



Photo 11: Vertical crack on internal wall.



Photo 12: Vertical crack on internal wall.



Photo 13: Horizontal crack above window.



Photo 14: Vertical crack on internal wall.




Photo 15: Major vertical-diagonal crack on the internal bedroom wall.



Photo 16: Horizontal crack above window.



Photo 17: Dampness on internal brick wall.



Photo 18: Diagonal crack on the internal bedroom wall above window.

Project:
ETS-CM-010836-WN:
Professional Consultancy Services
for House Van Dyk in Jeffreys
Bay in the Sarah Baartman
District
 – STRUCTURAL ENGINEERING
 DISCIPLINE

Report Title:
 Structural Engineering
 condition Assessment Report

Report Sub-Title:
HOUSE VAN DYK
 PHOTOGRAPHIC REPORT

Revision: **02**

Date: **21.05.2024**



Page:
Page 18



Photo 1: Vertical crack on internal wall.



Photo 2: Dampness on internal brick wall.



Photo 3: Dampness on internal brick wall.



Photo 4: Diagonal crack on the internal bedroom wall above window.



Photo 5: Timber roof trusses



Photo 6: Timber roof trusses



Photo 7: Cracks on external brick wall above window.




Photo 8: No aprons or stormwater around the building.




Photo 9: No roof gutters or rain water downpipe.

Project:
ETS-CM-010836-WN:
Professional Consultancy Services
for House Van Dyk in Jeffreys
Bay in the Sarah Baartman
District
 – STRUCTURAL ENGINEERING
 DISCIPLINE

Report Title:
 Structural Engineering
 condition Assessment Report

Report Sub-Title:
HOUSE VAN DYK
 PHOTOGRAPHIC REPORT

Revision: **02**

Date: **21.05.2024**



Page:
Page 19



Photo 1: Cracks on floor tiles.



Photo 2: Cracks on floor tiles.



Photo 3: Algae and moulds has developed on the surface of the brick walls.



Photo 4: Delamination of floor tiles.



Photo 5: Delamination of joint sealant.



Photo 6: Algae and moulds has developed on the surface of the brick walls.



Photo 7: Delamination of joint sealant.



Photo 8: Delamination of joint sealant.



Photo 9: Garage floor tiles

Project:
ETS-CM-010836-WN:
Professional Consultancy Services
for House Van Dyk in Jeffreys
Bay in the Sarah Baartman
District
 – STRUCTURAL ENGINEERING
 DISCIPLINE

Report Title:
 Structural Engineering
 condition Assessment Report

Report Sub-Title:
HOUSE VAN DYK
 PHOTOGRAPHIC REPORT

Revision: **02**

Date: **21.05.2024**



Page:
Page 20



Photo 1: General site view.



Photo 2: General site view.



Photo 3: Boundary wall.



Photo 4: No aprons around the building .



Photo 5: Boundary wall.



Photo 6: Boundary wall.



Photo 7: Typical site soil material. It appears the founding material has clay content.



Photo 8: Typical site soil material. It appears the founding material has clay content.




Photo 9: Lateral Movement. External wall of the main bedroom

Appendix D: Geotechnical Field Report

**GEOTECHNICAL INVESTIGATION FOR
58 PRIDE OF INDIA CRESCENT, WAVECREST,
JEFFREYS BAY**

HOUSE VAN DYK



Prepared By:



Prepared For:



Document prepared by:

Dwala Group Pty Ltd

2014/223042/07

F +27 86 552 2337

E nhlanhla@dwalagroup.com

W dwalagroup.com

A person using Dwala Group documents or data accepts the risk of:

- a) Using the documents or data in electronic form without requesting and checking them for accuracy against the original hard copy version.
- b) Using the documents or data for any purpose not agreed to in writing by Dwala Group.

Document control			
Report title	Geotechnical report for the proposed remedial works for a deforming house (House van Dyk)		
Client	National Home Builders Registration Council (NHBRC)		
Date	15 February 2023	Keywords	
Compiled by	Lethabo Moatshe	Fill	Collapsible
Approved by:	Nhlanhla Magigaba	Concrete apron	Water Leakage
Rev		00	

Contents

EXECUTIVE SUMMARY	i
1. Introduction	1
2. Available information	1
3. Site locality and description	2
4. Climate	3
5. Investigation Methodology	4
5.1 Test pitting	4
5.2 Laboratory testing	4
6. Geology	5
7. Results of Investigation	6
7.1 Fill horizon	7
7.2 Mudrock bedrock	7
8. Groundwater conditions	7
9. Plumbing Services	7
10. Laboratory tests	7
10.1 Foundation Indicators	8
11. Geotechnical Considerations	9
11.1 Shallow seepage/groundwater level	9
11.2 Collapsible soil profile	9
11.3 Compressible Soil Profile	9
12. Current Site Conditions	10
12.1 Foundation conditions	10
12.2 Concrete Apron	10
12.3 Leaking plumbing services	11
12.4 Water damping conditions	12
12.5 Structural conditions	13
13. Engineering Geological Zoning	16
14. Conclusions	17
15. Recommendations	18
15.1 Foundations	18

15.2	Soil Moisture Stabilisation	18
15.3	Professional Indemnity	19
16.	References	20

Appendices

Appendix A

Summary of Standard Soil and Rock Profile Description Terminology

Appendix B

Soil Profile Descriptions

Appendix C

Laboratory Test Results

Appendix D

Settlement Calculations

Appendix E

Site plan

Figures

Figure 1:	Showing the investigated house in Wavecrest, Jeffreys Bay (red outline).	2
Figure 2:	Showing the topography, vegetation and decorative stone cover on the site.	3
Figure 3:	Showing the general geology map of the site; (Geological Survey, printed by the Government Printer, Pretoria, 2019).	5
Figure 4:	Showing the test pit profiles on site.	6
Figure 5:	Showing the absence of a concrete apron on the north and the portion on the west side of the investigated house.	11
Figure 6:	Showing the water damage on the bedroom walls, wardrobe and damp bathroom walls.	12
Figure 7:	Showing the horizontal, vertical and diagonal cracks on the interior walls, floor and ceiling skirt around the investigated house.	14
Figure 8:	Showing the cracks on the exterior walls around the investigated house.	15

Tables

Table 1:	Test pit summary	4
Table 2:	Test pit profile summary	6
Table 3:	Summary of Foundation Indicator test results	8
Table 4:	Geotechnical Characteristics	16

EXECUTIVE SUMMARY

NHBRC appointed Dwala Group to carry out a geotechnical investigation for a deforming structure (House van Dyk). The study area is situated at 58 Pride of India Crescent, Wavecrest in Jeffreys Bay, Eastern Cape Province. The geotechnical investigation comprised of desktop study, fieldwork (test pit excavation, soil profiling, and sampling of selected horizon for laboratory testing), laboratory testing and reporting.

The main objective of the investigation was to investigate the cause of the deformation in the existing structure, evaluate the founding conditions, and give recommendations for remedial actions.

The geological profile revealed that the site is underlain by fill and mudrock bedrock.

Zone C2: This zone covered the entire site and is characterized by potentially collapsible and compressible fill and completely weathered mudrock (silty sands, sandy material). The expected total settlement for this zone is greater than 10 mm and a differential movement that is 75% (**C2**).

The strip footings are placed directly on a thin layer of sandy fill material which is potentially collapsible and compressible and as such, no measures were put in place to prevent collapse settlement on the site.

Based on the soil profile characteristics and the condition of the structure, it is evident that the structure should have been founded either on a foundation of substantial stiffness if it had to perform satisfactorily. This would have required a soil raft of non-active material placed on a concrete raft foundation with high stiffness. This solution would typically be combined with limited articulation and a substantial brick force specification.

Due to the fact that the foundation material below the foundation is collapsible and compressible, the underpinning of the foundation is considered suitable for strengthening the foundation.

Measures to attempt to stabilise future soil moisture change and hence curb further movement as effectively as possible must be implemented.

1. Introduction

NHBRC appointed Dwala Group to carry out a geotechnical investigation for a deforming structure (House van Dyk). The study area is situated at 58 Pride of India Crescent, Wavecrest in Jeffreys Bay, Eastern Cape Province. Fieldwork, carried out on the 27th of January 2023, included excavation of test pits, soil profiling, soil sampling, and exposing existing foundations of the structure to assess the possible factors that might be causing the house to deform (crack).

The objectives of the geotechnical investigation were to:

- Present a discussion on the prevailing condition of the structure.
- Determine the stratigraphy of the site and its geotechnical properties.
- To determine whether any problem soils are present at the site that could have had an effect on either founding or construction methods for the structure to deform (crack).
- To delineate the site into appropriate geotechnical zones according to any essential differences in founding conditions encountered.
- To evaluate the founding conditions at the site and to recommend building precautions necessary for different geotechnical zones.
- To obtain basic data concerning the use of the in-situ materials for guideline purposes.
- To present findings and recommend measures to restrict or reduce further structural distress in the structure.

The approach to the investigation was to assess the status quo in terms of the characteristics of the soil profile and the measures implemented (if any) to protect the structure against potential differential movements. This is followed by recommendations on appropriate rectification measures.

2. Available information

At the time of the investigation, the following information was available:

- The 1:50 000 scale geological map of Humansdorp sheet 3424BB (Council for Geosciences, 2019).
- Aerial photographs, sourced from Google Earth®.

3. Site locality and description

The proposed site is situated at 58 Pride of India Crescent in Wavecrest, Jeffreys Bay located in the Eastern Cape Province. It can be accessed via main road R102, onto St Francis Street, Seetuin Road, Dr A D Keet Road onto Pride of India Cres which forms the eastern boundaries of the site. The house is approximately 6 km north of Jeffreys Bay Main Beach. The area consists of residential developments. Figure 1 below shows the site locality of the investigated house.




Figure 1: Showing the investigated house in Wavecrest, Jeffreys Bay (red outline).

Topographically the site is moderately sloping at an angle of approximately 7° towards the northeast.

The investigated house is covered by pavement on the driveway (southeast), south side and southwest corner of the house. The garden area on the north side of the house is covered by grass, some trees and flowers with a portion on the northeast corner of the house covered by decorative stones as shown in Figure 2 below.



Figure 2: Showing the topography, vegetation and decorative stone cover on the site.

4. Climate

The climate in Jeffreys Bay is warm and temperate. The climate of the area is classified as Cfb by the Köppen-Geiger system. The temperature here averages 17.7°C. Rain falls in Jeffrey's Bay throughout the year with the lowest precipitation in May, averaging 39 mm. In November, the precipitation reaches its peak, with an average of 60 mm. The rainfall is approximately 565 mm annually (Climate-data.org: 2012).

The Weinert Climatic N-number for the area (Weinert, 1980) is <5, which indicates that the climate is semi-humid to humid and chemical weathering processes are dominant.

5. Investigation Methodology

The geotechnical investigation comprised desktop study, fieldwork, laboratory testing and analysis and reporting.

5.1 Test pitting

To meet the requirements for a stand to be registered with NHBC the investigation was carried out in accordance with the specification for geotechnical site investigations for housing developments (National Department of Housing specification GFSH- 2).

Fieldwork included excavation and profiling of two (2 No.) test pits. A two-person team carried out the test pitting in order to comply with accepted safety requirements as reflected in the Site Investigation Code of Practice (SAICE, 2010). The test pits were set out and profiled by a team of engineering geologists/ geotechnical engineers in accordance with South African standards (Standards South Africa. South African. National Standard. Profiling, Percussion Borehole and Core Logging in Southern Africa SANS 633:2012). Test pit details are summarised in Table 1 below.

Table 1: Test pit summary

Test Pit No	Coordinates (WGS84)		Depth (m)	Remarks
	Latitude	Longitude		
HD1	34° 0'50.61"S	24°54'49.96"E	1.10	Refusal on soft mudrock bedrock
HD2	34° 0'50.39"S	24°54'50.55"E	0.80	Refusal on soft mudrock bedrock

5.2 Laboratory testing

Representative samples were recovered and submitted to the SANAS-accredited Engineering Laboratory in Gqeberha for testing. Soil testing included the determination of the Foundation Indicators (comprising sieve and hydrometer grading analyses and Atterberg Limits) as well as the determination of in-situ moisture content.

6. Geology

According to a 1:50 000 scale geological map of the Humansdorp sheet 3424BB (Council for Geoscience, 2019), the investigated site is underlain by mudrock and sandstone of the Ceres Subgroup of the Bokkeveld Group of the Cape Supergroup as shown in Figure 3 below.




Figure 3: Showing the general geology map of the site; (Geological Survey, printed by the Government Printer, Pretoria, 2019).

7. Results of Investigation

The detailed descriptions of the soil profiles encountered in the test pits are presented in Appendix B; while the soil profiles for the whole site are summarised below in Table 2.

Table 2: Test pit profile summary

Test Pit No:	Brick Wall	Concrete Foundation	Fill horizon	Mudrock bedrock
HD1	0 – 0.10	0.10 – 0.35	0.35 – 0.60	0.60 – 1.10
HD2	0 – 0.10	0.10 – 0.30	0.30 – 0.40	0.40 – 0.80

Figure 4 below shows the test pits excavated on-site. The profile on-site comprises the following:

- Fill horizon; and
- Mudrock bedrock



Figure 4: Showing the test pit profiles on site.

7.1 Fill horizon

A fill horizon was encountered in the two (2 No.) test pits excavated on site. The layer comprises slightly moist, greyish brown patched olive green, red and black, clayey sand with sub-angular gravel, pebbles, and sparse rubble and waste. The horizon has a consistency that is medium-dense. The thickness of the horizon varies from 0.25 m in test pit HD1 to 0.10 m in test pit HD2.

7.2 Mudrock bedrock

The mudrock bedrock was encountered in the two (2 No.) test pits excavated on site. It occurs as completely to highly weathered, orangey-brown mottled black and red, very closely jointed, laminated, very fine-grained, very soft rock. Refusal was encountered in all the test pits on soft mudrock.

8. Groundwater conditions

Groundwater seepage was not encountered in the test pits excavated on site.

9. Plumbing Services

The plumbing services of the house are located above ground on the south side of the house. Initially, the pipes were located underground until a water leakage occurred allowing water to flow underground into the foundations. An excess amount of water leaked underground into the foundations in a short space of time which was seen from the water bill.

10. Laboratory tests

Representative samples of the materials encountered on site were taken and submitted to a soils laboratory where they were subjected to the following tests:

- Grading and Atterberg Limits including moisture content.

The laboratory results are attached as Appendix C to this report.

10.1 Foundation Indicators

Representative samples were collected for laboratory testing and submitted for foundation indicator tests. The test results are attached in Appendix C and summarised in Table 3 below.

Table 3: Summary of Foundation Indicator test results

Hole no.	Depth (m)	Soil composition				GM	Atterberg limits			Activity	Moisture Content	Unified soil classification
		Clay (%)	Silt (%)	Sand (%)	Gravel (%)		LL (%)	PI (%)	LS (%)			
Fill horizon												
HD1	0.35 – 1.10	4.0	26.0	38.0	32.0	1.37	20.0	8.0	4.0	Low	18.2	SC
Completely weathered mudrock bedrock												
HD2	0.40 – .50	10.0	23.0	44.0	23.0	1.16	26.0	10.0	5.0	Low	17.5	SC

Where:

GM	=	Grading modulus
LL	=	Liquid Limit
PI	=	Plasticity Index
WPI	=	Weighted Plasticity Index (PI x % passing the 0.425 mm sieve)
LS	=	Linear Shrinkage
Activity	=	Expansiveness of the soil according to Van der Merwe's method
SC	=	Clayey sand

Table 3 above indicates that:

The **fill material** underlying the site consists of clayey sand (**SC**) with a moisture content of 18.2%. The horizon has a very high grading modulus of 1.37. The fine fractions of this material also exhibit a low (20.0%) liquid limit as well as low (4.0%) linear shrinkage. The plasticity index (PI) of the soil is low (12.0%). The material has a low potential expansiveness, according to the method proposed by Van der Merwe (1973).

The **completely weathered mudrock** underlying the site consists of clayey sand (**SC**) with a moisture content of 17.5%. The horizon has a high grading modulus of 1.16. The fine fractions of this material also exhibit a moderate (26.0%) liquid limit as well as a low (5.0%) linear shrinkage. The plasticity index (PI) of the soil is low (10.0%). The material has a low potential expansiveness, according to the method proposed by Van der Merwe (1973).

11. Geotechnical Considerations

The following constraints, as proposed by Partridge, Wood, and Brink (1993), have to be considered for the classification of this site.

11.1 Shallow seepage/groundwater level

Groundwater seepage was not encountered in the test pits excavated on site.

11.2 Collapsible soil profile

The foundation indicator test results (see Section 10) indicate that the fill horizon material and the completely weathered mudrock bedrock on-site comprise coarse-grained soils of 70% in the fill material and 67% in the completely weathered mudrock material. Coarse-grained soils are prone to collapse upon wetting and additional loading.

The coarse materials of the fill and completely weathered mudrock bedrock where the foundations of the investigated house are placed underwent collapse settlement when water was introduced into the foundations from the water leakage that occurred and the additional load of the house.

11.3 Compressible Soil Profile

The foundation indicator test results (see Section 10) indicate that the fill horizon material and the completely weathered mudrock bedrock on-site comprise fine-grained soils of 30% in the fill material and 33% in the completely weathered mudrock.

The fine materials of the fill and completely weathered mudrock bedrock where the foundations of the investigated house are placed underwent settlement when the moisture conditions under the foundations' changed due to the water leakage that occurred.

12. Current Site Conditions

12.1 Foundation conditions

Inspection of the foundations of the investigated house showed that the house is founded on “strip footings” of a limited thickness (averages at 0.23 m), width and depth, probably representing a low-stiffness ground beam or a low-stiffness raft if cast integrally with the floor slab. **The strip footings are placed directly on potentially collapsible and compressible fill that is medium-dense and very soft mudrock bedrock material.** The soil profile at the excavated test pit indicates that no proper measures (e.g. densification of fill and completely weathered mudrock materials/ improvement of the collapsible soil profile and/or replacement with an engineered fill) were put in place to prevent settlement. **The stiffness of the foundations is inadequate to withstand the differential settlement that inevitably occurred due to the collapsible settlement of the materials.**

The strip footing foundation is thin with a varying thickness between 200 mm in test pit HD2 to 250 mm in test pit HD1. This foundation is considered to be inadequate to withstand collapse settlement, however, the structural engineer will confirm the suitability of the footing.

Furthermore, the sandy fill material where the foundations are placed is very thin ranging from 0.25 m in test pit HD1 to 0.10 m in test pit HD2. These materials collapsed when the moisture conditions changed from dry to moist due to the water infiltration from seasonal rainfall and water leakage from plumbing services. **This horizon was found to be wet (moisture content of 18.2%), and the infiltration of water into this medium-dense horizon resulted in the collapse of the horizon.**

12.2 Concrete Apron

The function of a concrete apron around a building is to protect the foundations and the soil under and around it from water and prevent it from directly infiltrating into the foundations by draining them away to prevent foundation movement and structural damage.

The southeast portion of the house which is the driveway is covered with intact brick pavement which protects the foundations from water infiltration.

The northwest, southwest corner and south sides of the house are covered by decorative stones which are loosely placed and do not drain water away or prevent water from directly infiltrating into the foundations. These decorative stones prove not to be effective in preventing ingress of water.



Figure 5: Showing the absence of a concrete apron on the north and the portion on the west side of the investigated house.

The north, south and west sides of the house do not have a concrete apron around them to prevent the water from directly infiltrating into the foundations and draining them away from the foundations as shown in Figure 5 above which is detrimental to the foundations as they are not protected from water ingress.

The absence of an effective concrete apron around the investigated house allowed water to permeate the soil directly and infiltrate through to the foundations saturating the soil around and underneath the foundations. This triggered the movement of foundations which resulted in the collapse settlement of the foundations and structural damage to the house.

12.3 Leaking plumbing services

In reference to the discussions with the homeowners, it was indicated that the plumbing on the south side of the house (along the side of the main bathroom) was initially underground until a water leakage occurred allowing water to flow underground into the foundations. An excess amount of water leaked underground in a short space of time which was seen from the water bill. This excess water infiltrated the soil underlying the house, putting pressure on the foundation and exacerbating the failure of the house resulting in cracks and structural damage.

During the site inspection, it was found that the house foundation was built on collapsible soil material, this assessment was based on the nature of structural damages observed on the brick wall around the structure and the soil profile underlying the site. This is problematic since inter alia seasonal moisture changes in the foundation and sub-foundation horizons of especially lightly loaded fixed structures give rise to volumetric changes. Volumetric change in the soil skeleton in turn induces stresses in the footings and super-structure, leading to super-structure strain and cracking. Due to the repetitive nature of the stress variation, conventional crack repair measures generally are unsuccessful.

12.4 Water damping conditions

The walls and wardrobe of the main bedroom and the grouting of the tiles in the main bathroom are visibly damp due to water damage as can be seen in Figure 6 below which the homeowners have tried to curb using moisture absorbers placed in the wardrobes.




Figure 6: Showing the water damage on the bedroom walls, wardrobe and damp bathroom walls.

12.4.1 Walls and grouting of tiles affected by water damping

As the property was been exposed to a leaking pipe, damping occurred resulting in water damage to the bedroom walls, and bathroom tiles (on the walls and floors). Water damping does damage to interior walls, and the grout between the tiles weakens the tile adhesive and saturates the subfloor, as was seen in this property. After penetrating dampness, grout can crack or deteriorate even in well-designed tile flooring, leading the tiles to come loose. It is likely that the grouting was weakened by the standing water, thus leading to damp walls and flooring. It is essential that the house be cleaned up because if the walls and floors remain damp over some time, mould growth can develop, and tiles may weaken and become loose.

12.4.2 Cupboards affected by water damping

Water damping has resulted in damage to the wardrobes in the main bedroom. The interior of the wardrobe is damaged and may require replacement. The direct contact with moisture has caused a slight change in the appearance of the wardrobe. Joints have also loosened and the wood itself is warped with some minor cracks. The damage to wood can progress from slight to severe in only a few days. If left unattended these cabinets can develop mould because of long exposure to water and especially if they remain damp for a long period.

12.5 Structural conditions

The house under assessment displayed structural distress (lateral and vertical movement) because of heave and ultimately differential settlement. Cracks were observed on the interior walls, the floor, the ceiling and the ceiling skirt, above the sliding door and bedroom doors and extending from the corners of the windows and doors as shown in Figure 7 below.



Figure 7: Showing the horizontal, vertical and diagonal cracks on the interior walls, floor and ceiling skirt around the investigated house.

Horizontal cracks were also observed on the exterior walls of the house and some extending from the windows as shown in Figure 8 below.



Figure 8: Showing the cracks on the exterior walls around the investigated house.

The homeowners indicated that one of the bedroom doors which has a visible crack above the door frame was stuck and could not open. The jammed doors and the observed cracks around the investigated house are an indication of foundation movement and settlement. It is worth noting that this site has most likely experienced collapse settlement.

Based on the soil profile characteristics on the site and the condition of the structures, it is evident that the structures should have been founded either on a foundation of substantial stiffness if it had to perform satisfactorily. This would have required a soil raft of non-active material of about 1.50 m in thickness, or a concrete raft foundation with high stiffness. These solutions would typically be combined with limited articulation and a substantial brick force specification.

13. Engineering Geological Zoning

For urban planning purposes, the site is zoned according to the NHBRC classification systems. Due to the presence of potentially expansive and compressive soil horizons under the entire site, the site has been delineated into one geotechnical zone. The descriptions of this zone are as follows:

Zone C2: This zone covered the entire site and is characterized by potentially collapsible and compressible thin fill horizon and completely weathered mudrock (silty sands, sandy material). The expected total settlement for this zone is greater than 10 mm and a differential movement that is 75% (**C2**).

Table 4: Geotechnical Characteristics

Geotechnical Characteristics				
Typical Founding Material	Character of Founding Material	Expected Range of Total Soil Movements (Mm)	Assumed Differential Movement (% of Total)	Site Class
Silty sands, sands, sandy and gravelly soils	Compressible And	<5,0	75%	C
	Potentially	5,0-10,0	75%	C1
	Collapsible Soils	>10,0	75%	C2

The expected immediate total settlement of the foundations in test pit HD1 (west side of the house) is **12.00 mm** on the thin fill material based on a founding depth of 0.35 m, a strip footing width of 1.01 m and an in-situ stiffness of 7 MPa (using the method proposed by Janbu et.al, 1956).

The expected immediate total settlement of the foundations in test pit HD2 (north side of the house) is **10.00 mm** on the thin fill material based on a founding depth of 0.30 m, a strip footing width of 0.85 m and an in-situ stiffness of 7 MPa (using the method proposed by Janbu et.al, 1956).

A settlement that is 10 mm or larger is likely to be a differential settlement and may compromise the structure of the development.

The allowable bearing capacity (FoS=3) of this material is approximately 73 kPa.

14. Conclusions

The conclusion of the investigation can be summarised as follows:

- The horizontal and diagonal cracks indicate movement of the foundations and water ingress.
- The fill and completely weathered mudrock material comprise predominantly clayey sand material.
- The laboratory tests indicate that the soil profile has low potential expansiveness, however, it **is potentially collapsible and compressible due to the sandy nature of the materials.**
- Settlement calculations show that upon loading and change in moisture content of the soils (from partially saturated to a fully saturated state) on site, the settlement for the site is approximately **11.0 mm.**
- Current foundations are placed directly on medium-dense, thin clayey sand fill that is not well densified and as such, no measures were put in place to prevent settlement of the collapsible soils underlying the site. The strip footings were not adequate to handle the large settlement that was experienced on the site due to the collapsible and compressible soils.
- **The structural distress which is observed on this site can mainly be ascribed to the differential settlement, which is a result of collapsible and compressible material below the founding level.**
- **The north, south and west sides of the house have no effective moisture barrier/apron. Concentration and discharging of rainwater, via downpipes, against to structure has increased the risk of differential settlement.**
- **The leakage of the plumbing services that occurred on the site exacerbated the structural failure of the house.** It caused the damping of the bedroom walls and tile joints in the main bathroom.
- Cracks smaller than 0.5 mm could have been caused by a combination of settlement and temperature differences. Other factors may have contributed, but it is difficult to determine (e.g. moisture content in masonry bricks).

15. Recommendations

Plans for the buildings have not been obtained to study the footing details. However, for purposes of prescribing rectification measures and based on what we have seen first-hand of the actual footings, this information is not critical:

The approach followed in the rectification process represents a dichotomy, viz:

- Underpinning;
- Incorporating measures to attempt stabilising future soil moisture change and hence curb heave/shrinkage movement as effectively as possible; and
- Protecting the structure against additional potential movement by strengthening the superstructure where necessary, but at the same time providing flexibility to it by way of movement joints (these recommendations will be done by a structural engineer).

15.1 Foundations

Due to the fact that the foundation material below the foundation is potentially collapsible and compressible, the **underpinning of the foundation should be considered and investigated**. There is a risk of cracking during the process and the shrinkage of the fresh concrete, but this will stabilize with time. It is also difficult to underpin the internal walls. Should the client select this option, the structural engineer can prepare a detailed procedure for the process.

15.2 Soil Moisture Stabilisation

Water must be kept away from the foundations. To stabilise the soil moisture around the foundations of the house an adequate apron of approximately 1.50 m width must be constructed around the house in such a way that water does not pond anywhere directly next to the structure of the house. This will require draping of the soil before placing the apron. **When carrying out the above it must be confirmed that no services are leaking.**

In addition, while a garden may be established near the buildings, no large trees should be planted near the buildings. Watering plants close to the house may have a negative effect on the moisture stabilisation below the foundation.

15.3 Professional Indemnity

Dwala Group has not carried out detailed construction supervision or design and therefore accepts no responsibility for the design and/or failures and consequences, therefore, that may occur in the future. We would, however, like to assist with recommendations for the repair of the structure.

The recommendations and methods of construction must be finalised with a contractor. It must be emphasised that all measures to render an existing structure crack free, is certainly more difficult to incorporate than in the case of a new structure still to be built. Although there is no guarantee against minor and isolated cracks developing subsequent to the implementation of these measures, a high success rate is possible, particularly to the extent of maintaining a high degree of aesthetical appeal.

16. References

1. Geological Survey (Council for Geoscience), 2019. 1:250 000 Geological Map Sheet #3424BB Humansdorp.
2. Geotechnical Investigations for Housing Developments, Generic Specifications GFSH-2, September 2002.
3. <https://en.climate-data.org/africa/south-africa/eastern-cape/jeffreys-bay-7174/> [Accessed on 30 January 2023]
4. Jennings, J E B, Brink, A B A and Williams, A A B, (1973). Revised Guide to Soil Profiling for Civil Engineering Purposes in Southern Africa. The Civil Engineer in S A, p 3-12. January 1973.
5. National Home Builders Registration Council, Home Building Manual, Part 1 & 2. First revision, February 1999.
6. Partridge TC, Wood CK and Brink ABA “Priorities for urban expansion within the PWV metropolitan region: The primacy of geotechnical constraints”. South African Geographical Journal, Vol. 75, pp 9 – 13. . 1993.
7. South African National Standard. *Profiling, Percussion Borehole and Core Logging in Southern Africa*. SANS 633:2012.
8. Site Investigation Code of Practice, 1st Edition, South African Institution of Civil Engineering - Geotechnical Division, January, 2010.
9. South African Loading Code SANS 10160 Basis for structural design and actions for buildings and industrial structures – Part 4: Seismic actions and general requirements for buildings, 2011.
10. Wagner A.A., 1957, “The use of unified soils classification system by Bureau of Reclamation”, Proceedings of the 4th ICSMFE, London, Vol 1:125
11. Weinert, H.H. 1980. The Natural Road Construction Materials of Southern Africa. Academica. Pretoria.

Appendix A

Summary of Standard Soil and Rock Profile Description Terminology

STANDARD DESCRIPTIONS USED IN SOIL PROFILING

1. MOISTURE CONDITION		2. COLOUR	
Term	Description	The Predominant colours or colour combinations are described including secondary coloration described as banded, streaked, blotched, mottled, speckled or stained.	
Dry			
Slightly moist	Requires addition of water to reach optimum moisture content for compaction		
Moist	Near optimum content		
Very Moist	Requires drying to attain optimum content		
Wet	Fully saturated and generally below water table		
3. CONSISTENCY			
3.1 Non-Cohesive Soils		3.2 Cohesive Soils	
Term	Description	Term	Description
Very Loose	Crumbles very easily when scraped with geological pick	Very soft	Easily penetrated by thumb. Sharp end of pick can be pushed in 30 - 40mm. Easily moulded by fingers.
Loose	Small resistance to penetration by sharp end of geological pick	Soft	Pick head can easily be pushed into the shaft of handle. Moulded by fingers with some pressure.
Medium Dense	Considerable resistance to penetration by sharp end of geological pick	Firm	Indented by thumb with effort. Sharp end of pick can be pushed in up to 10mm. Can just be penetrated with an ordinary spade.
Dense	Very high resistance to penetration to sharp end of geological pick. Requires many blows of hand pick for excavation.	Stiff	Penetrated by thumbnail. Slight indentation produced by pushing pick point into soil. Cannot be moulded by fingers. Requires hand pick for excavation.
Very Dense	High resistance to repeated blows of geological pick. Requires power tools for excavation	Very Stiff	Indented by thumbnail. Slight indentation produced by blow of pick point. Requires power tools for excavation.
4. STRUCTURE		5. SOIL TYPE	
		5.1 Particle Size	
Term	Description	Term	Size (mm)
Intact	Absence of fissures or joints	Boulder	>200
Fissured	Presence of closed joints	Pebbles	60 – 200
Shattered	Presence of closely spaced air filled joints giving cubical fragments	Gravel	60 – 2
Micro-shattered	Small scale shattering with shattered fragments the size of sand grains	Sand	2 – 0,06
Slickensided	Polished planar surfaces representing shear movement in soil	Silt	0,06 – 0,002
Bedded Foliated	Many residual soils show structures of parent rock.	Clay	<0,002
6. ORIGIN		5.2 Soil Classification	
6.1 Transported Soils			
Term	Agency of Transportation		
Colluvium	Gravity deposits		
Talus	Scree or coarse colluvium		
Hillwash	Fine colluvium		
Alluvial	River deposits		
Aeolian	Wind deposits		
Littoral	Beach deposits		
Estuarine	Tidal – river deposits		
Lacustrine	Lake deposits		
6.2 Residual soils			
These are products of in situ weathering of rocks and are described as e.g. Residual Shale			
6.3 Pedocretes			
Formed in transported and residual soils etc. calcrete, silcrete, manganocrete and ferricrete.			

SUMMARY OF DESCRIPTIONS USED IN ROCK CORE LOGGING

1. WEATHERING				
Term	Symbol	Diagnostic Features		
Residual Soil	W5	Rock is discoloured and completely changed to a soil in which original rock fabric is completely destroyed. There is a large change in volume.		
Completely Weathered	W5	Rock is discoloured and changed to a soil but original fabric is mainly preserved. There may be occasional small corestones.		
Highly Weathered	W4	Rock is discoloured, discontinuities may be open and have discoloured surfaces, and the original fabric of the rock near the discontinuities may be altered; alteration penetrates deeply inwards, but corestones are still present.		
Moderately Weathered	W3	Rock is discoloured, discontinuities may be open and will have discoloured surfaces with alteration starting to penetrate inwards, intact rock is noticeably weaker than the fresh rock.		
Slightly Weathered	W2	Rock may be slightly discoloured, particularly adjacent to discontinuities, which may be open and will have slightly discoloured surfaces, the intact rock is not noticeably weaker than the fresh rock.		
Unweathered	W1	Parent rock showing no discolouration, loss of strength or any other weathering effects.		
2. HARDNESS			3. COLOUR	
Classification	Field Test	Compressive Strength Range MPa	The predominant colours or colour combination are described including secondary colouration described as banded, streaked, blotched, mottled, speckled or stained.	
Extremely Soft Rock	Easily peeled with a knife	<1		
Very Soft Rock	Can be peeled with a knife. Material crumbles under firm blows with the sharp end of a geological pick.	1 to 3		
Soft Rock	Can be scraped with a knife, indentation of 2 to 4 mm with firm blows of the pick point.	3 to 10		
Medium Hard Rock	Cannot be scraped or peeled with a knife. Hand held specimen breaks with firm blows of the pick.	10 to 25		
Hard Rock	Point load tests must be carried out in order to distinguish between these classifications	25 - 70		
Very Hard Rock	These results may be verified by uniaxial compressive strength tests on selected samples.	70 - 200		
Extremely Hard Rock		>200		
4. FABRIC				
4.1 Grain Size		4.2 Discontinuity Spacing		
Term	Size (mm)	Description for: Bedding, foliation, laminations	Spacing (mm)	Descriptions for joints, faults, etc.
Very Coarse	>2,0	Very Thickly Bedded	> 2000	Very Widely
Coarse	0,6 – 2,0	Thickly Bedded	600 – 2000	Widely
Medium	0,2 – 0,6	Medium Bedded	200 – 600	Medium
Fine	0,06 – 0,2	Thinly Bedded	60 – 200	Closely
Very Fine	< 0,06	Laminated	3 – 60	Very closely
		Thinly Laminated	<3	
5. ROCK NAME			6. STRATIGRAPHIC HORIZON	
Classified in terms of origin:				
IGNEOUS	Granite, Diorite, Gabbro, Syenite, , Dolerite, Trachyte, Andesite, Basalt.			Identification of rock type in terms of stratigraphic horizons.
METAMORPHIC	Slate, Felsite, Gneiss, Schist, Quartzite			
SEDIMENTARY	Shale, Mudstone, Siltstone, Sandstone, Dolomite, Conglomerate, Tillite, Limestone.			

Appendix B

Soil Profile Descriptions




DWALA GROUP
No Limitations

National Home Builders Registration Council (NHBRC)
House van Dyk

HOLE No: HD1
Sheet 1 of 1

JOB NUMBER: 100150



NOTES

- 1) Sidewalls are stable.
- 2) Refusal on soft mudrock.
- 3) No groundwater seepage was intercepted.
- 4) FI and MC sample taken at 0.35--0.60 m depth.
- 5) The footing is placed at a depth of 0.35 m and has a thickness of 0.25 m and a width of 1.01 m.

CONTRACTOR :
MACHINE : Pick and shovel
DRILLED BY :
PROFILED BY : LM
TYPE SET BY : LM
SETUP FILE : STANDARD.SET

INCLINATION :
DIAM :
DATE :
DATE : 27/01/2023
DATE : 08/02/2023 10:26
TEXT : ..s\HouseVanDykLogs1.0.txt

ELEVATION :
X-COORD :
Y-COORD :

HOLE No: HD1
Jeffreys Bay




DWALA GROUP
No Limitations

National Home Builders Registration Council (NHBRC)
House van Dyk

HOLE No: HD2
Sheet 1 of 1

JOB NUMBER: 100150



NOTES

- 1) Sidewalls are stable.
- 2) Refusal on soft mudrock.
- 3) No groundwater seepage intercepted.
- 4) FI and MC sample taken at 0.40--0.80 m depth.
- 5) The footing is placed at a depth of 0.30 m and has a thickness of 0.20 m and a width of 0.85 m.

CONTRACTOR :
MACHINE : Pick and shovel
DRILLED BY :
PROFILED BY : LM
TYPE SET BY : LM
SETUP FILE : STANDARD.SET

INCLINATION :
DIAM :
DATE :
DATE : 27/01/2023
DATE : 08/02/2023 10:26
TEXT : ..s\HouseVanDykLogs1.0.txt

ELEVATION :
X-COORD :
Y-COORD :

HOLE No: HD2
Jeffreys Bay



DWALA GROUP
No Limitations

National Home Builders Registration Council (NHBRC)
House çan Dyk

LEGEND
Sheet 1 of 1

JOB NUMBER: 100150

	SAND	{SA04}
	CLAYEY	{SA09}
	MUDROCK	{SA12}
	ÓÜÔSY ÇĖŠŠ	{SA14}
	CONCRETE	{SA34}
Name ●	DISTURBED SAMPLE	{SA38}
⊗ ⊗	ROOTS	{SA40}

CONTRACTOR :
MACHINE :
DRILLED BY :
PROFILED BY :

TYPE SET BY : LM
SETUP FILE : STANDARD.SET

INCLINATION :
DIAM :
DATE :
DATE :

DATE : 08/02/2023 10:26
TEXT : ..s\HouseVanDykLogs1.0.txt

ELEVATION :
X-COORD :
Y-COORD :

LEGEND
SUMMARY OF SYMBOLS

Appendix C

Laboratory Test Results



Outeniqua Lab EC cc.

Materials Testing Laboratory

Registration No. 2009/230653/23

170 Sidwell Avenue, Sidwell, Port Elizabeth : PO Box 3186, George Industria, 6536

Tel: 041 4512464 : Fax: 041 4534959 : e-mail: luwayne@outeniqualab.co.za / agovender@outeniqualab.co.za

R-FIND-1-6

Feb 21


Customer :	Dwala Group (Pty) Ltd	Project :	House Van Dyk
	66 Ingersol Road	Date Received :	27/01/23
	Lynnwood Glen - Pretoria	Date Reported :	06/02/23
Attention :	0081, South Africa	Req. Number :	47/23
	Lethabo Moatshe - 0813487547	No. of Pages :	1/2

TEST REPORT



FOUNDATION INDICATOR - (TMH 1 Method A1(a),A2,A3,A4,A5) & (ASTM Method D422)

Material Description:	Dark Brown - Clayey Silty Gravelly Sand	Sample Number:	16581		
Position:	HD1	Liquid Limit	20	Linear Shrinkage	4
Depth (m):	0,35-1,1	Plasticity Index	8	Insitu M/C%	18,2

Sieve Size(mm)	% Passing
75,0	100
63,0	100
53,0	100
37,5	100
26,5	97
19,0	96
13,2	93
9,5	90
6,7	85
4,75	80
2,36	70
1,18	65
0,600	63
0,425	62
0,075	31
0,0690	31
0,0494	28
0,0223	26
0,0065	23
0,0049	13
0,0035	9
0,0025	5
0,0015	3



% Clay	4	% Silt	26	% Sand	38	% Gravel	32
Unified Soil Classification		SC		PRA Soil Classification		A-2-4	



Notes:

- Specimens delivered to Outeniqua Lab in good order.

L Malgraff (Member)
For Outeniqua Lab EC cc.

1. The test results are reported with an approximate 95% level of confidence.
2. This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Technical Director of Outeniqua Lab.
3. Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and/or taken.
4. Measuring Equipment, traceable to National Standards is used where applicable.
5. While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.



Registration No. 2009/230653/23

170 Sidwell Avenue, Sidwell, Port Elizabeth : PO Box 3186, George Industria, 6536


Tel: 041 4512464 : Fax: 041 4534959 : e-mail: luwayne@outeniqualab.co.za / agovender@outeniqualab.co.za

Customer :	Dwala Group (Pty) Ltd	Project :	House Van Dyk
	66 Ingersol Road	Date Received :	27/01/23
	Lynnwood Glen - Pretoria	Date Reported :	06/02/23
Attention :	0081, South Africa	Req. Number :	47/23
	Lethabo Moatshe - 0813487547	No. of Pages :	2/2



TEST REPORT
FOUNDATION INDICATOR - (TMH 1 Method A1(a),A2,A3,A4,A5) & (ASTM Method D422)

Material Description:	Dark Brown - Clayey Silty Sand	Sample Number:	16582		
Position:	HD2	Liquid Limit	26	Linear Shrinkage	5
Depth (m):	0,4-0,8	Plasticity Index	10	Insitu M/C%	17,5

Sieve Size(mm)	% Passing
75,0	100
63,0	100
53,0	100
37,5	100
26,5	100
19,0	97
13,2	95
9,5	92
6,7	88
4,75	85
2,36	79
1,18	74
0,600	72
0,425	71
0,075	34
0,0699	34
0,0500	31
0,0225	29
0,0065	28
0,0047	25
0,0034	19
0,0025	12
0,0014	8



% Clay	10	% Silt	23	% Sand	44	% Gravel	23
Unified Soil Classification		SC		PRA Soil Classification		A-2-4	



Notes:

- Specimens delivered to Outeniqua Lab in good order.

L Malgraff (Member)
For Outeniqua Lab EC cc.

- The test results are reported with an approximate 95% level of confidence.
- This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Technical Director of Outeniqua Lab.
- Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and/or taken.
- Measuring Equipment, traceable to National Standards is used where applicable.
- While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.


Appendix D

Settlement Calculations


PREDICTION OF THE AVERAGE ELASTIC SETTLEMENT OF A STRIP FOOTING

PROJECT NAME	House van Dyk
PROJECT NUMBER	100150
PROBLEM DESCRIPTION	HD1-Settlement on In-Situ Materials
LOCATION	Jeffreys Bay

INPUT PARAMETER	LAYER 1	LAYER 2	UNIT
FOUNDING DEPTH (D)	0,35	0,35	m
WIDTH OF THE FOOTING (B)	1,01	1,01	m
DEPTH OF LAYER (H1, H2)	0,6	1,1	m
STIFFNESS OF COMPRESSIBLE STRATUM	7	7	MPa
FOUNDATION PRESSURE (q)	150	150	kPa
H / B	0,59	1,09	
D / B	0,35	0,35	
U ₁ - INFLUENCE FACTOR	0,38	0,58	
U ₀ - INFLUENCE FACTOR	0,98	0,98	
AVERAGE IMMEDIATE SETTLEMENT ***	8	4	mm
TOTAL IMMEDIATE SETTLEMENT PREDICTED		12	mm




*** - After Janbu, Bjerrum and Kjaernsli




PREDICTION OF THE AVERAGE ELASTIC SETTLEMENT OF A STRIP FOOTING

PROJECT NAME	House van Dyk
PROJECT NUMBER	100150
PROBLEM DESCRIPTION	HD2-Settlement on In-Situ Materials
LOCATION	Jeffreys Bay

INPUT PARAMETER	LAYER 1	LAYER 2	UNIT
FOUNDING DEPTH (D)	0,3	0,3	m
WIDTH OF THE FOOTING (B)	0,85	0,85	m
DEPTH OF LAYER (H1, H2)	0,4	0,8	m
STIFFNESS OF COMPRESSIBLE STRATUM	7	7	MPa
FOUNDATION PRESSURE (q)	150	150	kPa
H / B	0,47	0,94	
D / B	0,35	0,35	
U ₁ - INFLUENCE FACTOR	0,31	0,54	
U ₀ - INFLUENCE FACTOR	0,98	0,98	
AVERAGE IMMEDIATE SETTLEMENT ***	6	4	mm
TOTAL IMMEDIATE SETTLEMENT PREDICTED		10	mm



*** - After Janbu, Bjerrum and Kjaernsli



Appendix E

Site plan

